


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Kingman County. Sec. 5 Twp. 30S Rge. 7 E/W
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines
C NW SE

Lease Owner Monsanto Company
Lease Name Young Well No. 1
Office Address 3545 N.W. 58th St. Oklahoma City, OK 73112
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole
Date Well completed October 21, 1980
Application for plugging filed Verbal Application 19
Application for plugging approved Verbal Approval 19
Plugging commenced October 21, 1980
Plugging completed October 21, 1980
Reason for abandonment of well or producing formation



Locate well correctly on above
Section Plot

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well William T. Owen
Producing formation Depth to top Bottom Total Depth of Well
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	266'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy rotary mud from 4285 ft. (rotary total depth) to 260 ft. Set plug at 260 ft. and cemented with 40 sacks cement. Filled hole with heavy rotary mud from 260 ft. to 60 ft. Set solid plug at 60 ft. and cemented to cellar with 10 sacks cement, 10 sacks cement in rat hole.

Plugging operations accomplished utilizing Halliburton Oil Well cementing pump truck through 4 1/2 inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Services
410 Union Center Bldg., Wichita, KS 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.
Dean Britting, Agent (employee of owner) ~~owner~~ ~~operator~~

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting
251 N. Water, Wichita, KS 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of October, 19 80

My commission expires July 25, 1982

Elsie Willison
Elsie Willison Notary Public.

KANSAS DRILLERS LOG

COMPANY Monsanto Company

SEC. 5 T. 30S R. 7W

FARM Young NO. 1

LOC. C NW SE

COUNTY Kingman

ROTARY TOTAL DEPTH 4285'

COMM. October 12, 1980

COMP. October 21, 1980

CONTRACTOR H-30, Inc. (Rig #3)

ISSUED October 27, 1980

CASING

10 3/4"

8 5/8" Set at 266' w/300 sxs cement

5 1/2"

4 1/2"

ELEVATION 1477' K.B.

FIGURES INDICATE BOTTOM OF FORMATIONS

Red Bed and Shale	1130'
Shale and Lime	2150'
Lime and Shale	2358'
Shale and Lime	2565'
Lime and Shale	4285'
Rotary Total Depth	4285'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.


H-30, INC.

Gary Younger
Gary Younger

State of Kansas)
) ss.
County of Sedgwick)

Subscribed and Sworn to before me a Notary Public in and for

said county and state this 27th day of October, 1980.



Elsie Willison
Elsie Willison - Notary Public

My Commission Expires:

July 25, 1982