

15-095-00284-0000


STATE OF KANSAS CORPORATION COMMISSION

Give All Information Completely Make Required Affidavit Mail or Deliver Report to: Conservation Division State Corporation Commission 211 No. Broadway Wichita, Kansas

WELL PLUGGING RECORD

Kingman County. Sec. 5 Twp. 30S Rge. (#) 7 (W) Location as "NE/CNW/SW" or footage from lines SW SW NW Lease Owner Pickrell Drilling Company Lease Name Render "B" Well No. 1 Office Address 705 Fourth Nat'l Bank Bldg. Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole Date well completed November 15, 19 57 Application for plugging filed November 15, 19 57 Application for plugging approved November 15, 19 57 Plugging commenced November 15, 19 57 Plugging completed November 15, 19 57 Reason for abandonment of well or producing formation D & A

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19 Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives Producing formation Depth to top Bottom Total Depth of Well 4243 Feet Show depth and thickness of all water, oil and gas formations.

Table with columns: OIL, GAS OR WATER RECORDS and CASING RECORD. Includes columns for FORMATION, CONTENT, FROM, TO, SIZE, PUT IN, and PULLED OUT. One entry shows size 8 5/8" and put in 160'.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.


Filled with heavy mud to 160' bridge hole and cement with 20 sacks cement. Then heavy mud to 35 ft. below ground level bridge hole and cement with 10 sacks cement to bottom of cellar.

(If additional description is necessary, use BACK of this sheet) Name of Plugging Contractor Pickrell Drilling Company Address 705 Fourth Nat'l Bank Bldg.

STATE OF Kansas, COUNTY OF Sedwick, ss. Carl W. Sebitts (Signature) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Carl W. Sebitts 705 Fourth Nat'l Bank Bldg. (Address)

SUBSCRIBED AND SWORN to before me this 2nd day of December, 1957



Notary Public. My commission expires July 30, 1958

DEC 3 1957 CONSERVATION DIVISION Wichita, Kansas

PLUGGING FILE SEC 5 T. 30 R. 7 W BOOK PAGE 62 LINE 4

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company

Rotary Drilling Commenced 11/2/57

LOCATION: SW SW NW Sec. 5-30-7W

Rotary Drilling Completed 11/15/57

CONTRACTOR: Render B-1  
PICKRELL DRILLING COMPANY  
Wichita, Kansas

CASING RECORD: 4 jts. 160' 8 5/8" Spiralweld Casing cemented with 125 sacks cement circulated.

Filled with heavy mud 160' bridge hole and cemented with 20 sacks cement, then heavy mud to 35 feet bottom ground level, bridge hole and cement with 10 sacks cement to bottom of cellar.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

Red Rock	160'	Circ. for samples at	4125
Red Rock & Shale	660		4150
Shale & Shells, Lime	1240		4163
Lime & Shale	1520		4186
Lime	1840		4197
Lime & Shale	2925		4207
Lime & Sand	3151		4220
Lime, Sand & Shale	3275		4243
Shale & Sand	3360		
Lime & Shale	3479		
Lime	3902		
Lime & Shale	4140		
Mississippi	4197		
Lime	4243 T.D.		

S.L.M. at 2000 - O.K.  
3000 - "  
4000 - "

Slope Test at 2000 0° off  
3000 0° off  
4000 0° off

PLUGGING  
FILE # SEC 5 T 30 R 7W  
BOOK PAGE 62 LINE 4

The undersigned, Lloyd R. Pickrell, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

STATE COUNTY OF SEDGWICK

PICKRELL DRILLING COMPANY

DEC 3 1957

By Lloyd R. Pickrell  
Attorney-in-Fact

STATE OF KANSAS }  
COUNTY OF SEDGWICK }

ss.: CONSERVATION DIVISION  
Wichita, Kansas

On this 20 day of November, 19 57, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared Lloyd R. Pickrell to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: July 30, 1958

Deborah J. Hite  
Notary Public