

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

6/82

API NUMBER 15-119-20,386 ³⁴⁴⁻⁰⁰⁰⁰ (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Mesa Petroleum Co. OPERATORS LICENSE NO. 5575

ADDRESS P.O. Box 2009, Amarillo, Texas 79189 PHONE # (806) 378-1000

LEASE (FARM) HEINSON WELL NO. 1-27 WELL LOCATION SW NW COUNTY Meade

SEC. 27 TWP. 33 RGE. 28 or TOTAL DEPTH 6030' PLUG BACK TO 5941'

Check One:

OIL WELL _____ GAS WELL D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 1513' CEMENTED WITH 900 SACKS

CASING SIZE 4 1/2" SET AT 6001' CEMENTED WITH 300 SACKS

PERFORATED AT 5887-5928'

CONDITION OF WELL: GOOD POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Set CIBP @ 5830' plus 20' cement, find
freepoint of 4 1/2" casing and cut off (est. 5000'), set 50 sx plug from 1563-1363', set
25 sx plug from 600'-300', set 10 sx plug from 40'-surface, cut off 3' below ground level.
(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? C-1
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN ASAP

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Bill McElya PHONE # (806) 378-1000

ADDRESS P.O. Box 2009, Amarillo, Texas 79189

PLUGGING CONTRACTOR Sargents Casing Pullers LICENSE NO. 6547

ADDRESS P.O. Box 506, Liberal, Kansas 67901 PHONE # (316) 624-7455

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: R. E. Markert

(Operator or Agent) RECEIVED

DATE: December 12, 1985

STATE CORPORATION COMMISS

12-16-1985
DEC 16 1985

XC: KCC (1), WF, CR, Reg, Acctg, Land, Expl., Partners

State of Kansas



JOHN CARLIN
MICHAEL LENNEN
MARGALEE WRIGHT
KEITH R. HENLEY
JUDITH A. McCONNELL
BRIAN J. MCLINE

Governor
Chairman
Commissioner
Commissioner
Executive Secretary
General Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Derby Building
202 West 1st Street
WICHITA, KANSAS 67202-1288

THIS NOTICE

MAR 16 1986

EXPIRES

December 16, 1985

WELL PLUGGING NOTICE

Heinson #1-27
SW NW
Sec. 27-33S-28W
Meade County

Mesa Petroleum Co.
P. O. Box 2009
Amarillo, TX 79189

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Sincerely,

William R. Bryson

William R. Bryson, Director

Please submit your proposal for plugging the above captioned well to
DIST. #1 302 West McArtor Dodge City, KS 67801 316-225-6760
five days prior to plugging the well (KAR-82-3-113).