

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
203 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 03/92

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-119-20586-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Samedan Oil Corporation KCC LICENSE # 04570 8/97
(owner/company name) (operator's)
ADDRESS 9400 N. Broadway, Suite 700 CITY Oklahoma City
STATE Oklahoma ZIP CODE 73114 CONTACT PHONE # (405) 475-2000
LEASE Mohler Unit WELL# 8 SEC. 29 T. 33S R. 28 (~~XXXX~~West)
- SW - SW - BW SPOT LOCATION/CCCC COUNTY Meade

2310 FEET (in exact footage) FROM N (circle one) LINE OF SECTION (NOT Lease Line)
330 FEET (in exact footage) FROM W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS
SURFACE CASING SIZE 8 5/8" SET AT 1510 CEMENTED WITH 1210 SACKS
PRODUCTION CASING SIZE 5 1/2" SET AT 5918 CEMENTED WITH 300 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: Perfs: 5,608' - 5,618'

ELEVATION 2363 G.L. T.D. 5919' PETD 5877 ANHYDRITE DEPTH _____
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING L.D. rod string. NU BOP. POOH w/tbg string. Run CIBP + 20' cmt. Set CIBP 50' above top perf. Circ hole w/plug mud. (9.2# 36 vis) L.D. tbg. NU to 5 1/2" csg free point and cut est +/-2500'. Pull 5 1/2" csg to +/-1560'. Mix and pump 80 sxs cmt 1560'-1360'. Pull 5 1/2" csg to +/-650'. Mix and pump 40 sxs cmt 650' to 550'. Pull 5 1/2" csg to +/-34'. Mix & pump 10 sxs cmt 34' - 4'. Cut off and weld steel I.D. plate 4' B.G.L.
(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes
If not explain why? N/A

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Lee Farmer PHONE# (405) 262-7778
ADDRESS Rt. 2, Box 218-B City/State El Reno, Oklahoma 73036

PLUGGING CONTRACTOR Sargent's Casing Pullers KCC LICENSE # 6547 6/97
(company name) (contractor's)
ADDRESS P. O. Box 506, Liberal, KS PHONE # (816) 624-7455

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) June 1997

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-123) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 6/9/97 AUTHORIZED OPERATOR/AGENT Debbie Kehr
(signature)

RECEIVED
KANSAS CORPORATION COMMISSION

SAMEDAN OIL CORPORATION

9400 North Broadway, Suite 700
OKLAHOMA CITY, OKLAHOMA 73114
(405-475-2000)

June 9, 1997

Kansas Corporation Commission
Conservation Division
130 South Market, Room 2078
Wichita, Kansas 67202

RE: Mohler Unit #8
Section 29-33S-28W
Meade County, Kansas


Gentlemen:

Enclosed please find Form CP-1 and a copy of the induction log.

If you require any additional information, please call me at (405) 475-2000.

Very truly yours,

SAMEDAN OIL CORPORATION



Debbie Kerr
Regulatory Clerk III

:dk

Enclosures

xc: D. K. Read File
Mohler Unit #8 Well File

RECEIVED
KANSAS CORP COMM
JUN 11 1997

Mohler Unit #8



**DUAL INDUCTION
GUARD LOG**

COMPANY FIELD PRINT
 WELL TRANK YOU
 FIELD State
 County

COMPANY MESA PETROLEUM CO
 WELL JOHANNSEN #1-29
 FIELD MOHLER NE
 COUNTY MEADE STATE KANSAS
 Location 2310' FNL & 350' W Other Service DSN-C
15-119-20586 c/c
 Sec. 29 Twp. 33S Rge. 28

Permanent Datum G.L. Elev. 2364.5'
 Log Measured From K.B. 13.5 Ft. Above Perm. Datum
 Drilling Measured From K.B.

Date	<u>10-7-82</u>			
Run No.	<u>ONE</u>			
Depth—Driller	<u>5924'</u>			
Depth—Welex	<u>5914'</u>			
Btm. Log Inter.	<u>5912'</u>			
Top Log Inter.	<u>1522'</u>			
Casing—Driller	<u>8 3/8" @ 1511'</u>	@	@	
Casing—Welex	<u>1522'</u>			
Bit Size	<u>7 7/8" @ T.D.</u>			
Type Fluid in Hole	<u>W.B. MUD</u> <u>CHEMICALS</u>			
Dens. Visc.	<u>9.0 52</u>			
pH Fluid Loss	<u>9.0 9.0 ml</u>		ml	ml
Source of Sample	<u>FLOWING</u>			
R _m @ Meas. Temp.	<u>0.80 @ 78 °F</u>	@	°F	@ °F
R _m @ Meas. Temp.	<u>0.67 @ 70 °F</u>	@	°F	@ °F
R _m @ Meas. Temp.	<u>0.90 @ 70 °F</u>	@	°F	@ °F
Source R _m R _m	<u>MEASURED</u>			
R _m @ BHT	<u>0.45 @ 137 °F</u>	@	°F	@ °F
Time Since Circ.	<u>6 HR</u>			
Max. Rec. Temp.	<u>137 °F @ 5880'</u>	°F @		°F @ °F
Equip. Location	<u>9689 LIB. KS</u>			
Recorded By	<u>K.A. JECK & R.L. SALLEY</u>			
Witnessed By	<u>MR. JAMES</u>			

**DO NOT REMOVE
FROM WELL FILE**



Kansas Corporation Commission

Bill Graves, Governor Timothy E. McKee, Chair Susan M. Seltsam, Commissioner John Wine, Commissioner
Judith McConnell, Executive Director David J. Heinemann, General Counsel

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

June 12, 1997

Samedan Oil Corporation -
9400 N Broadway Suite 700
Oklahoma City OK 73114

Mohler Unit #8
API 15-119-20,586
2310 FNL 330 FWL
Sec. 29-33S-28W
Meade County

Dear Lee Farmer,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams

David P. Williams
Production Supervisor

by sep

District: #1
304 W. McArtor
Dodge City, KS 67801
(316) 225-6760