

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
201 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 03/92

WELL PLUGGING APPLICATION FORM  
(PLEASE TYPE FORM and File ONE Copy)

API # 15-119-20,574-0001 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Samedan Oil Corporation KCC LICENSE # 04570 8/97

ADDRESS 9400 N. Broadway, Suite 700 (owner/company name) CITY Oklahoma City (operator's)

STATE Oklahoma ZIP CODE 73114 CONTACT PHONE # (405) 475-2000

LEASE Mohler Unit WELL# 17 SEC. 29 T. 33S R. 28 (East/West)

- NW - SW - SW SPOT LOCATION/QQQQ COUNTY Meade

986 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

230 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET#           

CONDUCTOR CASING SIZE 5 1/2 SET AT 1301 CEMENTED WITH            SACKS

SURFACE CASING SIZE 8 5/8 SET AT 1521 CEMENTED WITH Unknown SACKS

PRODUCTION CASING SIZE 5 1/2 SET AT 5747 CEMENTED WITH 165 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: Perfs: 5600'-5632'

ELEVATION 2350' G.L. T.D. 5749 PBD 5688 ANHYDRITE DEPTH             
(G.L./K.B.): (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Run CIBP + 20' cmt. Set CIBP 50' above top perfs. Displace hole +/- 2500'. Pull csg to +/- 1571'. Mix & pump 80 sxs cmt 15/1' to 13/1'. Pull 5 1/2 csg to +/- 650'. Mix & pump 40 sxs cmt. 650' to 550'. Pull 5 1/2" csg. to +/- 34'. Mix & pump 10 sxs cmt. 34' to 4'. Cut off & weld steel I.D. plate 4' below G.L.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

If not explain why? N/A

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS

Lee Farmer PHONE# (405) 262-7778

ADDRESS Rt. 2, Box 218-B City/State El Reno, Oklahoma 73036

PLUGGING CONTRACTOR Sargents Casing Pullers KCC LICENSE # 06547 6/97

ADDRESS P.O. Box 506, Liberal, KS 67705-0506 PHONE # (316) 624-7455

PROPOSED DATE AND HOUR OF PLUGGING (if known?) June 1997

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 6-9-97 AUTHORIZED OPERATOR/AGENT: Debbie Kerr  
(signature)

6-11-1997

RECEIVED  
KANSAS CORPORATION COMMISSION  
JUN 11 1997

**SAMEDAN OIL CORPORATION**

9400 North Broadway, Suite 700  
OKLAHOMA CITY, OKLAHOMA 73114  
(405-475-2000)

June 9, 1997

Kansas Corporation Commission  
Conservation Division  
130 South Market, Room 2078  
Wichita, Kansas 67202

RE: Mohler Unit #17  
Section 290-33S-28W  
Meade County, Kansas


Gentlemen:

Enclosed please find Form CP-1 and a copy of the induction log.

If you require any additional information, please call me at (405) 475-2000.

Very truly yours,

SAMEDAN OIL CORPORATION



Debbie Kerr  
Regulatory Clerk III

:dk

Enclosures

xc: D. K. Read File  
Mohler Unit #17 Well File

RECEIVED  
KANSAS CORP COMM  
JUN 11 1997

COMPANY: **SAMEDAN OIL CORPORATION**

WELL: **MOHLER UNIT #17**

FIELD: **MOHLER**

COUNTY: **MEADE** STATE: **KANSAS**

COUNTY: MEADE  
Field: MOHLER  
Location: 986' FSL & 230' FWL  
Well: MOHLER UNIT #17  
Company: SAMEDAN OIL CORPORATION

**Schlumberger**

\* PLATFORM EXPRESS \*  
ARRAY INDUCTION  
MICRORESISTIVITY - GR

986' FSL & 230' FWL	Elev.: K.B. 2355 F
	G.L. 2350 F
	D.F. 2354 F
Permanent Datum: <u>GROUND LEVEL</u>	Elev.: <u>2350 F</u>
Log Measured From: <u>KELLY BUSHING</u>	5.0 F above Perm. Datum
Drilling Measured From: <u>KELLY BUSHING</u>	

API Serial No. 15-119-205740001	SECTION 29	TOWNSHIP 33S	RANGE 28W
------------------------------------	---------------	-----------------	--------------

Logging Date	30-MAR-1996		
Run Number	1		
Depth Driller	5749 F		
Schlumberger Depth	5746 F		
Bottom Log Interval	5738 F		
Top Log Interval	1520 F		
Casing Driller Size @ Depth	8.625 IN @	1521 F	
Casing Schlumberger	1520 F		
Bit Size	7.875 IN		
Type Fluid In Hole	SALT GEL-STARCH		
Density	Viscosity	9.7 LB/G	189 S
Fluid Loss	PH	13.6 C3	9
Source Of Sample	FLOWLINE		
RM @ Measured Temperature	0.910 OHMM @	65 DEGF	
RMF @ Measured Temperature	0.728 OHMM @	65 DEGF	
RMC @ Measured Temperature	1.092 OHMM @	65 DEGF	
Source RMF	RMC	CALCULATED	CALCULATED
RM @ MRT	RMF @ MRT	0.503 @ 123	0.403 @ 123
Maximum Recorded Temperatures	123 DEGF	123	123
Circulation Stopped	Time	30-MAR-1996	4:30
Logger On Bottom	Time	30-MAR-1996	8:00
Unit Number	Location	3008	LIBERAL
Recorded By	MARTINO		
Witnessed By	LEE FARMER		



## Kansas Corporation Commission

Bill Graves, Governor Timothy E. McKee, Chair Susan M. Seltsam, Commissioner John Wine, Commissioner  
Judith McConnell, Executive Director David J. Heinemann, General Counsel

### NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

June 12, 1997

Samedan Oil Corporation  
9400 N Broadway Suite 700  
Oklahoma City OK 73114

Mohler Unit #17  
API 15-119-20,574 ~ 0001  
986 FSL 230 FWL  
Sec. 29-33S-28W  
Meade County

Dear Lee Farmer,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

Sincerely,

David P. Williams

David P. Williams  
Production Supervisor

by  
JLP

District: #1  
304 W. McArtor  
Dodge City, KS 67801  
(316) 225-6760