

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
203 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 03/92

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-119-20556-0001 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Samedan Oil Corporation KCC LICENSE # 04570
(owner/company name) (operator's)
ADDRESS 9400 N. Broadway, Suite 700 CITY Oklahoma City
STATE Oklahoma ZIP CODE 73114 CONTACT PHONE # (405) 475-2000
LEASE Mohler Unit WELL# 12 SEC. 29 T. 33S R. 28 (East, West)
- NW - NW - SW SPOT LOCATION/QQQQ COUNTY Meade

2310 FEET (in exact footage) FROM S (circle one) LINE OF SECTION (NOT Lease Line)
330 FEET (in exact footage) FROM W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# E-26,993

CONDUCTOR CASING SIZE SET AT CEMENTED WITH SACKS
SURFACE CASING SIZE 8 5/8" SET AT 1527 CEMENTED WITH 800 SACKS
PRODUCTION CASING SIZE 4 1/2" SET AT 5791 CEMENTED WITH 200 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: Perfs: 559' - 5618'

ELEVATION 2358 G.L. T.D. 5792' PSTD N/A ANHYDRITE DEPTH
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING NH BOP. POOH w/tbg string. Run CIBP + 20' cmt. Set CIBP 50' above top perf. Circ. hole w/plug mud (9.2" 36 vis). NO to 4 1/2" csg free point & cut est. +/-2500'. Pull 4 1/2" csg to +/-1577'. Mix & pump 80 sxs 1577' to 1377'. Pull 4 1/2" csg to +/-650'. Mix and pump 40 sxs cmt 650' to 550'. Pull 4 1/2" csg to +/-34'. Mix and pump 10 sxs cmt 34' to 4'. Cut off and weld steel I.D. plate 4' below G.L.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

If not explain why? N/A

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Lee Farmer PHONE# (405) 262-7778

ADDRESS Rte. 2, Box 218-B City/State El Reno, Oklahoma 73036

PLUGGING CONTRACTOR Sargent's Casing Pullers KCC LICENSE # 6547

ADDRESS P. O. Box 506, Liberal, KS 67705-0506 PHONE # (316) 624-7455

PROPOSED DATE AND HOUR OF PLUGGING (if known?) June 1997

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 6/9/97 AUTHORIZED OPERATOR/AGENT: [Signature]
(signature)

8/97

6-11-1997

RECEIVED
KANSAS CORP. COM.
197 JUN 11

6/97

SAMEDAN OIL CORPORATION

9400 North Broadway, Suite 700
OKLAHOMA CITY, OKLAHOMA 73114
(405-475-2000)

June 9, 1997

Kansas Corporation Commission
Conservation Division
130 South Market, Room 2078
Wichita, Kansas 67202

RE: Mohler Unit #12
Section 29-33S-28W
Meade County, Kansas


Gentlemen:

Enclosed please find Form CP-1 and a copy of the induction log.

If you require any additional information, please call me at (405) 475-2000.

Very truly yours,

SAMEDAN OIL CORPORATION



Debbie Kerr
Regulatory Clerk III

:dk

Enclosures

xc: D. K. Read File
Mohler Unit #12 Well File

RECEIVED
KANSAS CORP COMM
1997 JUN 11 P 1:46

GEARHART

DUAL INDUCTION LATEROLOG

Mohler Unit #12

*Note: 100%
These
are shallow
pay
zone*

FILING NO _____

COMPANY DONALD C. STAWSON OIL PRODUCER

WELL BLEHM 'A' #1

FIELD BORCHERS SOUTH

COUNTY MEADE STATE KANSAS

LOCATION 15-119-20556-0001
NW-NW-SW

OTHER SERVICE:
BHV
COL
CNL
WEL
X-PILOT

SEC 29 TWP 33S RGE 28W

PERMANENT DATUM GL ELEV 2358

LOG MEASURED FROM KB 6.0 FT ABOVE PERM DATUM

DRILLING MEASURED FROM KB

2364
2362
2358

Date	<u>JAN 22, 1982</u>		FIELD PRINT	
Run No	<u>ONE</u>			
Depth-Driller	<u>5792</u>	<u>5</u>		
Depth-Logger	<u>5786</u>	<u>1</u>		
Bottom Logged Interval	<u>5785</u>	<u>1</u>		
Top Logged Interval	<u>1520</u>	<u>1</u>		
Casing-Driller	<u>8 3/8 @ 1527</u>	<u>5</u>		
Casing-Logger	<u>1520</u>	<u>5</u>		
Bit Size	<u>7 7/8</u>	<u>5</u>		
Type Fluid in Hole	<u>fr mud</u>			
Density and Viscosity	<u>9.4</u> <u>69</u>			
PH and Fluid Loss	<u>10</u> <u>11.6</u> cc	cc		
Source of Sample	<u>flowline</u>			
Rm @ Meas Temp	<u>.83 @ 54 °F</u>	@ °F @		
Rmf @ Meas Temp	<u>.71 @ 65 °F</u>	@ °F @		
Rmc @ Meas Temp	<u>1.15 @ 65 °F</u>	@ °F @		
Source of Rmf and Rmc	<u>m m</u>			
Rm @ BHT	<u>.45 @ 124 °F</u>	@ °F @		
End Circulation	<u>0030</u>			
Logger on Bottom	<u>0900</u>			
Max Rec Temp. Deg. F.	<u>124</u> °F	°F		
Equip. No and Location	<u>LICORAL 7553</u>			
Recorded By	<u>BUTLER</u>			
Witnessed By	<u>MR B</u>			



Kansas Corporation Commission

Bill Graves, Governor Timothy E. McKee, Chair Susan M. Seltsam, Commissioner John Wine, Commissioner
Judith McConnell, Executive Director David J. Heinemann, General Counsel

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

June 12, 1997

Samedan Oil Corporation
9400 N Broadway Suite 700
Oklahoma City OK 73114

Mohler Unit #12
API 15-119-20,556 -0001
2310 FSL 330 FWL
Sec. 29-33S-28W
Meade County

Dear Lee Farmer,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P Williams by
jlp

David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City, KS 67801
(316) 225-6760