

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
203 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 03/92

WELL PLUGGING APPLICATION FORM  
(PLEASE TYPE FORM and File ONE Copy)

API # 15-119-20,602-0001 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Samedan Oil Corporation KCC LICENSE # 04570 8/97  
(owner/company name) (operator's)  
ADDRESS 9400 N. Broadway, Suite 700 CITY Oklahoma City  
STATE Oklahoma ZIP CODE 73114 CONTACT PHONE # (405) 475-2000  
LEASE Mohler Unit WELL# 16 SEC. 31 T. 33S R. 28 (East/West)  
- NE - NE - NE SPOT LOCATION/QCQC COUNTY Meade

4950 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)  
330 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET# E-26,993

CONDUCTOR CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS  
SURFACE CASING SIZE 8 5/8 SET AT 1483 CEMENTED WITH 550 SACKS  
PRODUCTION CASING SIZE 4 1/2 SET AT 5875 CEMENTED WITH 250 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: Perfs: 5608'-5650'

ELEVATION 2354 G.L. T.D. 5900 PBD 5818 ANHYDRITE DEPTH \_\_\_\_\_  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR \_\_\_\_\_ CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

PROPOSED METHOD OF PLUGGING NU BOP. POOH w/tbg. string. Run CIBP + 20' cmt. Set CIBP 50' above freepoint & cut est. +/- 2500'. Pull 4 1/2 csg. to +/- 1533'. Mix & pump 80 sxs cmt. 1533' to 1333'. Pull 4 1/2 csg to +/- 650'. Mix & Pump 40 sxs cmt 650' to 550'. Pull 4 1/2 csg to +/- 34'. Mix & pump 10 sxs cmt 34' to 4'. Cut off & weld on steel ID plate 4' below G.L.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

If not explain why? N/A

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Lee Farmer PHONE# (405) 262-7778

ADDRESS Rt. 2, Box 218-B, S City/State El Reno, Oklahoma 73036

PLUGGING CONTRACTOR Sargents Casing Pullers KCC LICENSE # 6547  
(company name) (contractor's)

ADDRESS P.O. Box 506, Liberal, KS 67705-0506 PHONE # (316) 624-7455

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) June 1997

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 6-9-97 AUTHORIZED OPERATOR/AGENT: [Signature]  
(signature)

6-11-1997  
RECEIVED  
KANSAS CORP COM  
1997 JUN 11 P 1:47 PM

**SAMEDAN OIL CORPORATION**

9400 North Broadway, Suite 700  
OKLAHOMA CITY, OKLAHOMA 73114  
(405-475-2000)

June 9, 1997

KANSAS CORP...  
1997 JUN 11 P 1:41

Kansas Corporation Commission  
Conservation Division  
130 South Market, Room 2078  
Wichita, Kansas 67202

RE: Mohler Unit #16  
Section 31-33S-28W  
Meade County, Kansas


Gentlemen:

Enclosed please find Form CP-1 and a copy of the induction log.

If you require any additional information, please call me at (405) 475-2000.

Very truly yours,

SAMEDAN OIL CORPORATION



Debbie Kerr  
Regulatory Clerk III

:dk

Enclosures

xc: D. K. Read File  
Mohler Unit #16 Well File

C

Mohler #16

Schlumberger

DUAL INDUCTION /SFL W/GR

CV

15-119-20602-0001

COMPANY: ZINKE & TRUMBO LTD  
WELL: LOLA DRENNAN # 1-31  
FIELD: Wordeman  
COUNTY: MEADE  
STATE: KANSAS

CONFIDENTIAL

LOCATION: 330 FNL 330 SFEL N2 N2 W2

SEC: 31 TWP: 33S RGE: 28W

PERMANENT DATUM: GL ELEVATIONS-  
ELEV. OF PERM. DATUM: 2354.0 ' KB: 2363.0 '  
LOG MEASURED FROM: KB DF: 2362.0 '  
9.0 ' ABOVE PERM. DATUM GL: 2354.0 '  
DRLG. MEASURED FROM: KB

DATE: 16 JAN 83  
RUN NO: 1

DEPTH-DRILLER: 5900.0 '  
DEPTH-LOGGER: 5305.0 '  
BTM. LOG INTERVAL: 5899.0 '  
TOP LOG INTERVAL: 1485.0 '  
CASING-DRILLER: 1483 '  
CASING-LOGGER: 1485 '  
CASING: 8-5/8  
BIT SIZE: 7-7/8

K.C.C. LIBRARY



## Kansas Corporation Commission

Bill Graves, Governor Timothy E. McKee, Chair Susan M. Seltsam, Commissioner John Wine, Commissioner  
Judith McConnell, Executive Director David J. Heinemann, General Counsel

### NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

June 12, 1997

Samedan Oil Corporation  
9400 N Broadway Suite 700  
Oklahoma City OK 73114

Mohler Unit #16  
API 15-119-20,602 -0001  
4950 FSL 330 FEL  
Sec. 31-33S-28W  
Meade County

Dear Lee Farmer,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

Sincerely,

*David P. Williams by jlp*

David P. Williams  
Production Supervisor

District: #1  
304 W. McArtor  
Dodge City, KS 67801  
(316) 225-6760