

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

119

API NUMBER 15-199-20,796-70000 (of this well)

(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR ENSIGN OPERATING CO. OPERATORS LICENSE NO. 04782
ADDRESS 621 Seventeenth Street, Ste 1800
Denver, Colorado 80293 PHONE # (303) 293-9999

LEASE (FARM) Wiens WELL NO. 1-35 WELL LOCATION SW/NW COUNTY Meade
SEC. 35 TWP. 33 RGE. 28 (X) or (W) TOTAL DEPTH 6093' PLUG BACK TD 3321'

Check One:

OIL WELL _____ GAS WELL D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 1541' CEMENTED WITH 750 SACKS
CASING SIZE 4 1/2" SET AT 3363' CEMENTED WITH 225 SACKS (TOC at 2536')
PERFORATED AT 3119 to 3126', 3147 to 3150'

CONDITION OF WELL: GOOD POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Displace 25x CSH and 2.5x cement
across perf's; Back-Off casing at 'free point'; Mud to 1590'; 50px
cement - 1590 to 1490'; Mud to 900'; 50px cement - 900 to 800'; Mud to
40'; 10 px cement - 40 to 3'; Cut off and cap surface casing.
(If additional space is needed use back of form).
IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN ASAP

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

REED WACKER
ENSIGN OPERATING CO. PHONE # (316) 276-3267

ADDRESS P.O. Box 937; Garden City, Ks. 67846

PLUGGING CONTRACTOR MIDWEST CASING LICENSE NO. 06497

ADDRESS P.O. Box F, 506 Ellis; Sublette, Ks. 67877 PHONE # (316) 675-8349

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Reed Wacker
(Operator AGENT)

DATE: 4/18/90

①



DUAL INDUCTION SHORT GUARD LOG

STATE RECEIVED APR 19 1990 INSERVED Wichita, Kansas COMPANY WELL FIELD COUNTY		COMPANY ENSIGH OPERATING COMPANY WELL WIENS NO. 1-35 FIELD WILDCAT COUNTY MEADE API NO. 15-119-20,798 LOCATION C 8W NW SEC. 35 TWP 33 S RGE 28 W		STATE K8 OTHER SERVICES DSNII/SDL HL	
PERMANENT DATUM C.L. ELEV. 2480 LOG MEASURED FROM K.B. 11 FT. ABOVE PERM. DATUM DRILLING MEASURED FROM K.B.		ELEV. : K.B. 2491 D.F. 2489 C.L. 2480			
DATE	10/31/89				
RUN NO.	ONE				
DEPTH-DRILLER	6093				
DEPTH-LOGGER	6084				
BTH, LOG INTER.	6078				
TOP LOG INTER.	SURFACE				
CASING-DRILLER	8 5/8 @ 1550	0	0	0	
CASING-LOGGER	1550				
BIT SIZE	7 7/8				
TYPE FLUID IN HOLE	CHEM-CEL				
DENS. VISC	8.8 165	1	1	1	
PH FLUID LOSS	10.0 19.8	1	1	1	
SOURCE OF SAMPLE	FLOWLINE				
RM @ MEAS. TEMP.	1.58 @ 60	0	0	0	
RHF @ MEAS. TEMP.	1.36 @ 60	0	0	0	
RHC @ MEAS. TEMP.	1.86 @ 60	0	0	0	
SOURCE RMF RHC	MEAS MEAS.	1	1	1	
RM @ BHT	0.78 @ 129	0	0	0	
TIME SINCE CIRC.	4.5 HRS				
TIME ON BOTTOM	08:34				
MAX. REC. TEMP.	129 @ TO	0	0	0	
EQUIP. LOCATION	2983 LIA	1	1	1	
RECORDED BY	CARR				
WITNESSED BY	HOREDOCK				



Kansas Corporation Commission

MIKE HAYDEN GOVERNOR
KEITH R. HENLEY CHAIRMAN
RICH KOWALEWSKI COMMISSIONER
MARGALEE WRIGHT COMMISSIONER
JUDITH MCCONNELL EXECUTIVE DIRECTOR
FRANK A. CARO, JR. GENERAL COUNSEL

THIS NOTICE
AUG 21 1990
EXPIRES

CONSERVATION DIVISION
SHARI FEIST ALBRECHT, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

May 21, 1990
NOTICE OF RECEIPT OF
WELL PLUGGING APPLICATION

Ensign Operating Co.
621 17th Street, Suite 1800
Denver, CO 80293

Wiens 1-35
SW/NW
Sec. 35-33-38W
Meade County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist Albrecht
Shari Feist Albrecht
Director

District: #1 304 W. McArtor
Dodge City, KS 67801
(316) 225-6760