

AFFIDAVIT AND COMPLETION FORM


ACO-1

This form must be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within five days after the completion of the well, regardless of how the well was completed. Circle one: Oil, gas, dry, SWD, OWWO, injection. Please type. Complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316) 263-3238.

OPERATOR Tom F. Marsh, Inc. API NO: 15-189-20,574-00-00
 ADDRESS P. O. Box 1869 COUNTY Stevens
Liberal, KS 67901 FIELD Panoma
 **CONTACT PERSON Nancy Hagar LEASE Bonnett
 PHONE 316-624-8141 PROD. FORMATION Council Grove
 PURCHASER Panhandle Eastern Pipe Line Company WELL NO. 1
 ADDRESS P. O. Box 1348 WELL LOCATION 200' FEL and 1320' FNL
Kansas City, MO 64141 200 Ft. from East Line and
1320 Ft. from North Line of

DRILLING CONTRACTOR DaMac Drilling the SEC. 8 TWP. 34S RGE. 38W
 ADDRESS P. O. Box 1164 **RECEIVED**
Great Bend, KS 67530 **STATE CORPORATION COMMISSION**
JUN 14 1982

PLUGGING CONTRACTOR CONSERVATION DIVISION
 ADDRESS Wichita, Kansas
 TOTAL DEPTH 3235 PBD 3232
 SPUD DATE 3-30-82 DATE COMPLETED 4-28-82
 ELEV: GR 3226 DF 3234 KB 3234



WELL PLAT
 (Quarter) or (Full) Section - Please indicate.

KCC
 KGS

MISC. _____

DRILLED WITH ~~(CABLE)~~ (ROTARY) (AIR) TOOLS
 Report of all strings set — surface, intermediate, production, etc. (New) / ~~(Used)~~ casing.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8	20#	626	65/35 poz Class H	250 150	6%gel, 2%cc, 1/4#D29 3%cc
Production	7-7/8"	5-1/2	14#	3234	35/65 poz 50/50 poz	500 150	6%gel, 12 1/2#kol, 1/4#D29 2%gel, 18%salt .75%TTC

LINER RECORD			PERFORATION RECORD		
Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
TUBING RECORD			3204-10' : 3190-96'		
Size	Setting depth	Packer set at	3167-74' : 3056-60'		
2-3/8	3200'	none	3031-10' : 3010-22'		
			3001-05' : 2993-95'		
			2985-81' : 2981-783'		
			2972-76' : 2960-64'		
			2950-54' : 2944-48'		
			2937-40'		

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD	
Amount and kind of material used	Depth Interval treated
Acidized with 4500' gal. 15% Non-F acid and 200 ball sealers	Same as above
Fraced with 121,000# . . gelled 220,000# 20/40 sand	

TEST DATE: 4-28-82		PRODUCTION	
Date of first production n/a	Producing method (flowing, pumping, gas lift, etc.) flowing	A.P.I. Gravity .730	
RATE OF PRODUCTION PER 24 HOURS	Oil 0 bbls.	Gas 1000 MCF	Water % 20 bbls.
Disposition of gas (vented, used on lease or sold) to be sold		Producing interval (s) 2937-3210'	

** The person who can be reached by phone regarding any questions concerning this information.
 A witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

Name of lowest fresh water producing stratum Ogalalla Depth 350
 Estimated height of cement behind pipe circulated

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Sand, Red Bed	0	2011		
Red Bed	2011	2377		
Red Bed, Lime	2377	2570		
Lime and Shale	2570	3235	RED	

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

A F F I D A V I T

STATE OF Kansas, COUNTY OF Seward SS,

Keith Hill OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS


OATH, DEPOSES AND SAYS:

THAT HE IS Agent FOR Tom F. Marsh, Inc.
 OPERATOR OF THE Bonnett LEASE, AND IS DULY AUTHORIZED TO MAKE THIS
 AFFIDAVIT FOR AND ON BEHALF OF SAID OPERATOR, THAT WELL NO. 1 ON SAID LEASE HAS
 BEEN COMPLETED AS OF THE 28 DAY OF April 19 82, AND THAT ALL
 INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH NOT.

(S) Keith Hill, Agent

SUBSCRIBED AND SWORN TO BEFORE ME THIS 10 DAY OF June 19 82



Nancy K. Hagar
 NOTARY PUBLIC

MY COMMISSION EXPIRES: _____