

CONFIDENTIAL

Operator: License # 5003
Name: McCoy Petroleum Corporation
Address: 3017 N. Cypress
City/State/Zip: Wichita, KS 67226-4003
Purchaser: Anadarko
Operator Contact Person: Steve O'Neill
Phone (316): 636-2737
Contractor: Name: Sweetman Drilling, Inc.
License: 5653
Wellsite Geologist: John Hastings
Designate Type of Completion
 New Well Re-Entry Workover
 Oil SWD SLOW Temp. Abd.
 Gas EKHR SIGW
 Dry Other (Core, MSW, Expl., Cathodic, etc)

4950 Feet from S35 (circle one) Line of Section
330 Feet from E35 (circle one) Line of Section
Footages Calculated from Nearest Outside Section Corner:
NE, SE, NW or SW (circle one)
Lease Name: Bane Trust "A" Well # 1-6
Field Name: _____
Producing Formation: Lower Morrow Sand
Elevation: Ground 3222 KB 3235
Total Depth 6400 PBD 6344
Amount of Surface Pipe Set and Cemented at 1472 Feet
Multiple Stage Cementing Collar Used? Yes No
If yes, show depth set 3090 Feet
If Alternate II completion, cement circulated from _____
feet depth to _____ w/ _____ sz cat.
Drilling Fluid Management Plan ALT I 3-27-96
(Data must be collected from the Reserve Pit)

If Workover/Re-Entry: old well info as follows:
Operator: _____
Well Name: _____
Comp. Date _____ Old Total Depth _____
Deepening _____ Re-perf. _____ Conv. to _____
Plug Back _____ PBD _____
Cemented _____ Docket No. _____
Dual Completion _____ Docket No. _____
Other (SWD or Inj?) Docket No. _____
11-5-95 11-17-95 12-6-95
Spud Date Date Reached TD Completion Date

Chloride content 2900 ppm Fluid volume 1420 bbls
Dehydrating method used Evaporation
Use of fluid disposal if hauled offsite: _____
Operator Name: _____
Lease Name: _____
Quarter Sec. _____ Twp. _____ S Rng. _____ E/W _____
County _____ Docket No. _____
RELEASED
CONFIDENTIAL
FROM CONFIDENTIAL

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information on side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: [Signature]
Title: Petroleum Engineer Date: 12-14-95
Subscribed and sworn to before me this 14th day of DECEMBER 1995.
Notary Public: [Signature]

K.C.C. OFFICE USE ONLY

F Letter of Confidentiality Attached
C Wireline Log Received
C Geologist Report Received

Distribution

KCC SWD/Rep KGPA
 KGS Plug Other (Specify)

W. D. HESS
NOTARY PUBLIC
STATE OF KANSAS
My Appt. Exp. July 20, 1998

Operator Name McCoy Petroleum Corporation Lease Name Bane Trust #1-6 Well # 1-6

Sec. 6 Twp. 34S Rpt. 38 East County Stevens West

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all drill stem tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface during test. Attach extra sheet if more space is needed. Attach copy of log.

Drill Stem Tests Taken Yes No (Attach Additional Sheets.)

Samples Sent to Geological Survey Yes No

Cores Taken Yes No

Electric Log Run (Submit Copy.) Yes No

List All E.Logs Run: See Attached

CASING RECORD New Used

Report all strings set-conductor, surface, intermediate, production, etc.

Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs./Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	12-1/4	8-5/8"	24#	1472'	Prem + Lgt	900	2%cc, 6#gil
Production		4-1/2"	10.5#	6394'	Prem + CLH	200	#Flo, 10#gil
DV Tool					Class "C" Prem + Cl C	300 75	2%cc 2%cc

ADDITIONAL CEMENTING/SQUEEZE RECORD

Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate				
<input type="checkbox"/> Protect Casing				
<input type="checkbox"/> Plug Back TD				
<input type="checkbox"/> Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type	Acid, Fracture, Shot, Cement Squeeze Record	
	Specify Footage of Each Interval Perforated	(Amount and Kind of Material Used)	Depth
4	6180-6202'		
4	6211-6222'		

TUBING RECORD

Size 2-3/8" Set At 6222 Packer At _____ Liner Run Yes No

Date of First, Resumed Production, SWD or Inj. waiting for pipeline connection Producing Method Flowing Pumping Gas Lift Other (Explain)

Estimated Production Per 24 Hours	Oil	Bbls.	Gas	Hcf	Water	Bbls.	Gas-Oil Ratio	Gravity
			<u>2,258</u>					

Disposition of Gas: Vented Sold Used on Lease (If vented, submit ACO-18.)

METHOD OF COMPLETION: Open Hole Perf. Dually Comp. Commingled Other (Specify)

Production Interval: 6180-6202
6211-6222

ORIGINAL

15-189-22005

McCoy Petroleum Corporation
Bane Trust "A" #1-6
NE NE NE Section 6-34S-38W
Stevens County, KS

CONFIDENTIAL

Page 2. ACO-1

DST #1 6183'- 6220' (Upper & Lower "Blue" Sands)
Misrun - Hit Bridge

DST #2 6183'- 6220' (Upper & Lower "Blue" Sands)
Open 30", SI 60", Open 60", SI 90"
1st Open: GTS 4 min.
Gauged thru 1" choke:
10" gauge: 725 MCF
20" gauge: 1,205 MCF
30" gauge: Plugged off 2" flowline - no gauge
2nd Open: Gauged thru 1-1/2" choke
10" gauge: 2,075 MCF
20" gauge: 2,503 MCF
30" gauge: 2,558 MCF
40" gauge: 2,675 MCF
50" gauge: 2,675 MCF
60" gauge: 2,798 MCF
Recovered: 210' Gassy Mud
FP: 351-548 / 535-652#
SIP: 1483-1489#

RECEIVED
STATE CORPORATION COMMISSION

DEC 18 1995

CONSERVATION DIVISION
WICHITA, KANSAS

KCC

DEC 15

CONFIDENTIAL

ELECTRIC LOGS

Heebner Shale	4153(-918)
Lansing	4263(-1028)
Stark Shale	4795(-1560)
Marmaton	4983(-1748)
Marmaton 'B'	5010(-1775)
Cherokee Shale	5279(-2044)
Atoka	5510(-2275)
Morrow Shale	5786(-2551)
Upper "Blue" Sand	6176(-2941)
Lwr "Blue" Sand	6211(-2976)
"Red" Sand	6239(-3004)
RTD	6400(-3165)
LTD	6397(-3162)

RELEASED

MAR 23 1998

FROM CONFIDENTIAL



HALLIBURTON
CONFIDENTIAL

P.O. BOX 951046
DALLAS, TX 75395-1046

INVOICE

INVOICE NO.	DATE
881244	11/06/1995

WELL LEASE NO / PROJECT	WELL / PROJECT LOCATION	STATE	OWNER		
BANE TRUST 11-6	STEVENS	KS	DAME		
SERVICE LOCATION	CONTRACTOR	JOB PURPOSE	TICKET DATE		
LIBERAL	SWEETMAN DRILLING	CEMENT SURFACE CASING	11/06/1995		
ACCT. NO.	CUSTOMER AGENT	VENDOR NO.	CUSTOMER P.O. NUMBER	SHIPPED VIA	FILE NO.
584530	EUGENE SALDGA			COMPANY TRUCK	99216

CONFIDENTIAL

DIRECT CORRESPONDENCE TO:

MOODY PETROLEUM CO
ATTN: KEITH MOODY
3017 N CYPRESS
WICHITA, KS 67226-4003

P.O. BOX 1398
LIBERAL, KS 67905-0000

DEC 15

REFERENCE NO.	DESCRIPTION	QUANTITY	UOM	UNIT PRICE	AMOUNT
000-117	CEMENTING POUND TRIP	20	MT	2.85	57.00
	DISCOUNT (BID)	27	0 %		15.39-
001-016	CEMENTING CASING	1472	FT	1.145	1,450.00
	DISCOUNT (BID)	27	0 %		397.15-
030-018	CEMENTING PLUG 5W, PLASTIC TOP	8	5/8 IN EA	130.00	1,040.00
	DISCOUNT (BID)	27	0 %		285.10-
030-019	CEMENTING PLUG 5W, PLASTIC BOT	8	5/8 IN EA	135.00	1,080.00
	DISCOUNT (BID)	27	0 %		367.45-
125-217	GUIDE SHOE - 8 5/8" BRD	1	EA	300.00	300.00
	DISCOUNT (BID)	25	0 %		75.00-
245-1950	INSERT FLOAT VALVE - 8 5/8" BRD	1	EA	171.00	171.00
	DISCOUNT (BID)	25	0 %		42.75-
27-815-19415	FILL UP UNIT 7" OD 5/8"	1	EA	64.00	64.00
	DISCOUNT (BID)	25	0 %		16.00-
41-804-61048	CENTRALIZER - 8-5/8 X 12-1/4	4	EA	61.00	244.00
	DISCOUNT (BID)	25	0 %		61.00-

***** CONTINUED ON NEXT PAGE *****

TERMS: If Customer does not have an approved open account with Halliburton, all sums due are payable in cash at the time of performance of services or delivery of equipment, products or materials. If customer has an approved open account, invoices are payable on the twentieth day after date of invoice. Customer agrees to pay interest on any unpaid balance from the date payable until paid at the highest lawful contract rate applicable, but never to exceed 18% per annum. In the event Halliburton employs an attorney for collection of any account, Customer agrees to pay attorney fees of 20% of the unpaid account, plus all collection and court costs.



HALLIBURTON CONFIDENTIAL

INVOICE NO.	DATE				
891244	11/06/1995				
WELL LEASE NO./PROJECT	STATE	OWNER			
NE TRUST 1-6	KS	SAME			
SERVICE LOCATION	CONTRACTOR	JOB PURPOSE	TICKET DATE		
FEDERAL	SWEETMAN DRILLING	CEMENT SURFACE CASING	11/06/1995		
CCT. NO.	CUSTOMER AGENT	VENDOR NO.	CUSTOMER PO. NUMBER	SHIPPED VIA	FILE NO.
4450	EUGENE BALOGA			COMPANY TRUCK	99216

ORIGINAL

DIRECT CORRESPONDENCE TO:
P.O. BOX 1598
FEDERAL, KS 67505-0000

MCCOY PETROLEUM CO
ATTN: KATH MCCOY
3017 N. DYPRESS
MICHITA, KS 67226-4000

REFERENCE NO.	DESCRIPTION	QUANTITY	UM.	UNIT PRICE	AMOUNT
001-018	CEMENTING CASING - 400 HRS	16	HR	235.00	3,760.00
	DISCOUNT - (BTD)	1	UNT		1,015.20
504-050	CEMENT - PREMIUM PLUS	250	SK	11.91	2,977.50
	DISCOUNT - (BTD)	27	0 %		808.92
507-210	CEMENT	150	LB	1.65	247.50
	DISCOUNT - (BTD)	27	0 %		66.82
508-291	GILSONITE BULK	900	LB	.40	360.00
	DISCOUNT - (BTD)	27	0 %		97.20
509-406	ANHYDROUS CALCIUM CHLORIDE	1	SK	36.75	36.75
	DISCOUNT - (BTD)	17	0 %		9.92
500-221	CEMENTING MATERIALS RETURNED	20	X	11.91	238.20
	DISCOUNT - (BTD)	27	0 %		64.31
500-306	MILEAGE CMTO MAT DEL OR RETURN	60.7	TMI	.95	75.00
	DISCOUNT - (BTD)	27	0 %		20.25
500-307	BULK SERVICE CHARGE	391	CFI	1.35	527.85
	DISCOUNT - (BTD)	27	0 %		142.51
500-306	MILEAGE CMTO MAT DEL OR RETURN	208.5	TMI	.93	198.08
	DISCOUNT - (BTD)	27	0 %		53.48
504-120	CEMENT - HALL LIGHT PREM PLUS	150	SK	10.56	1,584.00
	DISCOUNT - (BTD)	27	0 %		1,283.04
504-050	CEMENT - PREMIUM PLUS	200	SK	11.91	2,382.00

CONFIDENTIAL
***** CONTINUED ON NEXT PAGE *****

TERMS: If Customer does not have an approved open account with Halliburton, all sums due are payable in cash at the time of performance of services or delivery of equipment, products or materials. If customer has an approved open account, invoices are payable on the twentieth day after date of invoice. Customer agrees to pay interest on any unpaid balance from the date payable until paid at the highest lawful contract rate applicable, but never to exceed 18% per annum. In the event Halliburton employs an attorney for collection of any account, Customer agrees to pay attorney fees of 20% of the unpaid account, plus all collection and court costs.

REMIT TO:
P.O. BOX 951046
DALLAS, TX: 75395-1046

PER COPY
ALBUQUERQUE
INVOICE

JOB SUMMARY
HALLIBURTON



WELL CONFIDENTIAL

INVOICE NO.	DATE
881244	11/06/1995

WELL LEASE NO./PROJECT	WELL/PROJECT LOCATION	STATE	OWNER
BAILEY TRUST L-6	STEVENS	KS	SAME
SERVICE LOCATION	CONTRACTOR	JOB PURPOSE	TICKET DATE
LIBERAL	SWEETMAN DRILLING	OPENING SURFACE CASING	11/06/1995
ACCT NO.	CUSTOMER AGENT	VENDOR NO.	CUSTOMER P.O. NUMBER
554550	EUDENE SAPOKA		
		SHIPPED VIA	FILE NO.
		COMPANY TRUCK	99216

TOD'S AND ACCESSORIES	DATE	LOCATION	JOB STARTED	JOB COMPLETE
	11-5-95	LIBERAL, KS	11-7-95	11-7-95
DIRECT CORRESPONDENCE TO				
MEDDY DE PRODUCTION CO				
ATTN: KEITH MEDDY				
3037 N. CYPRESS				
MICHIGAN, KS 67226-4003				

REFERENCE NO.	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	AMOUNT
	DISCOUNT (C/D)	27.0%			643.14
508-391	DILSONITE BULK	1200 LB		40.00	480.00
	DISCOUNT (C/D)	27.0%			129.60
507-210	FLOCFEE	315 LB		1.55	516.45
	DISCOUNT (C/D)	27.0%			139.44
509-406	ANHYDROUS CALCIUM CHLORIDE	12 SK		36.75	441.00
	DISCOUNT (C/D)	27.0%			119.07
500-207	PUMIC SERVICE CHARGE	719 CFT		1.35	970.65
	DISCOUNT (C/D)	27.0%			262.07
500-306	MIFERENTINO MAT DEL OR-CONFIDENTIAL	65 TON		3.35	217.75
	DISCOUNT (C/D)	27.0%			58.45

INVOICE SUBTOTAL		20,506.95
DISCOUNT (C/D)		
INVOICE GROSS AMOUNT		20,506.95
1	250	10.11
1	250	06
1	250	32
2	150	32
2	100	32
KANSAS STATE SALES TAX		1,744.28
LIBERAL CITY SALES TAX		1,451.92
SEWARD COUNTY SALES TAX		1,451.92
SUMMARY		
VOLUMES		
REMARKS		
INVOICE TOTAL		24,152.81

TERMS: Customer does not have an approved open account with Halliburton, all sums due are payable in cash at the time of performance of services or delivery of equipment, products or materials. If customer has an approved open account, invoices are payable on the twentieth day after date of invoice. Customer agrees to pay interest on any unpaid balance from the date payable until paid at the highest lawful contract rate applicable but never to exceed 18% per annum. In the event Halliburton employs an attorney for collection of any account, Customer to exceed 18% per annum. In the event Halliburton employs an attorney for collection of any account, Customer to exceed 18% per annum. In the event Halliburton employs an attorney for collection of any account, Customer to exceed 18% per annum.

FORM HAL-1800-F



HALLIBURTON CONFIDENTIAL

INVOICE

INVOICE NO.	DATE
880756	11/17/1995

WELL/LEASE NO./PROJECT	WELL/PROJECT LOCATION	STATE	OWNER
JANE TRUST 1 & 6	STEVENS	KS	CAME
SERVICE LOCATION	CONTRACTOR	JOB PURPOSE	TICKET DATE
LIBERAL	SWEETMAN	CEMENT PRODUCTION CASING	11/17/1995
ACCT NO.	CUSTOMER AGENT	VENDOR NO.	CUSTOMER P.O. NUMBER
354850	BARYL J. HANSON		
			SHIPPED VIA
			COMPANY TRUCK
			FILE NO.
			99754

ORIGINAL

DIRECT CORRESPONDENCE TO

MCCOY PETROLEUM CO
 5110 KETH MCCOY
 3017 N CYPRESS
 WICHITA KS 67226-4009

P.O. BOX 1598
 LIBERAL KS 67901

REFERENCE NO.	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	AMOUNT
	PRICING AREA - MID CONTINENT				
000-117	MILEAGE CEMENTING ROUND TRIP	45 MI		2.85	128.25
		2 UNIT			
	DISCOUNT - (BID)	27.0 %			70.79
001-016	CEMENTING CASING	6410 FT		2,070.00	2,070.00
		2.21 UNIT			
	DISCOUNT - (BID)	27.0 %			558.90
007-161	MULT STAGE CEMENTING ADD STAGE	1 STD		1,400.00	1,400.00
		1 UNIT			
	DISCOUNT - (BID)	27.0 %			378.00
28	INSERT VALVE 4-1/2	1 EA		285.00	285.00
807-6316					
	DISCOUNT - (BID)	25.0 %			71.25
40	CENTRALIZER 4-1/2 X 7-7/8	4 EA		45.00	180.00
806-6004					
	DISCOUNT - (BID)	25.0 %			45.00
44	CLAMP LIMIT 4-1/2 HINGED	2 EA		10.00	20.00
806-72020					
	DISCOUNT - (BID)	25.0 %			5.00
71	MULT STAGE CMTR 4-1/2 (BR)	1 EA		2,790.00	2,790.00
813-80100					
	DISCOUNT - (BID)	10.0 %			279.00
350	HALLIBURTON WELD	79 EA		16.75	1,323.25
870-10802					
	DISCOUNT - (BID)	25.0 %			411.88

CONTINUED ON NEXT PAGE

TERMS: If Customer does not have an approved open account with Halliburton, all sums due are payable in cash at the time of performance of services or delivery of equipment, products or materials. If customer has an approved open account, invoices are payable on the twentieth day after date of invoice. Customer agrees to pay interest on any unpaid balance from the date payable until paid at the highest lawful contract rate applicable, but never to exceed 18% per annum. In the event Halliburton employs an attorney for collection of any account, Customer agrees to pay attorney fees of 20% of the unpaid account, plus all collection and court costs.

INVOICE

CONFIDENTIAL

INVOICE NO.

880756

11/17/1995

WELL LEASE NO./PROJECT		WELL/PROJECT LOCATION		STATE	OWNER	
NE TRUST 1-6		STEVENS		KS	SAME	
SERVICE LOCATION		CONTRACTOR		JOB PURPOSE		TICKET DATE
GERAL		SWEETMAN		CEMENT PRODUCTION CASING		11/17/1995
JOCT NO.	CUSTOMER AGENT	VENDOR NO.	CUSTOMER P.O. NUMBER	SHIPPED VIA	FILE NO.	
14550	DARYL J. HANSON			COMPANY TRUCK	99754	

ORIGINAL

DIRECT CORRESPONDENCE TO:

MCCOY PETROLEUM CO
ATTN: KETH MCCOY
3012 N CYPRESS
WICHITA, KS 67226-4008

P O BOX 1598
LIBERAL KS 67901

REFERENCE NO.	DESCRIPTION	QUANTITY	UM	UNIT PRICE	AMOUNT
75	PROP SET-FREE FALL-5 1/2 BRD & DIA 164MM	1	EA	760.00	760.00
	DISCOUNT-(BID)	10.0 %			76.00
018-317	SUPER FLUSH	12	SK	100.00	1,200.00
	DISCOUNT-(BID)	27.0 %			324.00
504-043	CEMENT - PREMIUM	200	SK	11.35	2,270.00
	DISCOUNT-(BID)	27.0 %			623.70
504-050	CEMENT - PREMIUM PLUS	250	SK	11.91	2,977.50
	DISCOUNT-(BID)	27.0 %			803.18
504-120	CEMENT - HALL LIGHT PREM PLUS	300	SK	10.36	3,108.00
	DISCOUNT-(BID)	27.0 %			839.16
507-210	FLOCELE	144	LB	1.65	237.60
	DISCOUNT-(BID)	27.0 %			64.15
507-270	B-AIR 1/2 POWDER	50	LB	3.25	162.50
	DISCOUNT-(BID)	27.0 %			43.88
507-775	HALAD-322	113	LB	7.00	791.00
	DISCOUNT-(BID)	27.0 %			213.57
508-127	EAL SEAL 60	19	SK	25.90	492.10
	DISCOUNT-(BID)	27.0 %			132.86
508-291	NILSONITE BULK	2000	LB	30.00	600.00
	DISCOUNT-(BID)	27.0 %			162.00
509-405	ANHYDROUS CALCIUM CHLORIDE	7	SK	35.75	250.25

***** CONTINUED ON NEXT PAGE *****

TERMS: If Customer does not have an approved open account with Halliburton, all sums due are payable in cash at the time of performance of services or delivery of equipment, products or materials. If customer has an approved open account, invoices are payable on the twentieth day after date of invoice. Customer agrees to pay interest on any unpaid balance from the date payable until paid at the highest lawful contract rate applicable, but never to exceed 18% per annum. In the event Halliburton employs an attorney for collection of any account, Customer agrees to pay attorney fees of 20% of the unpaid account, plus all collection and court costs.

COPY
INVOICE



P.O. BOX 1578
DALLAS, TX 75395-1046

INVOICE NO.	DATE
880754	11/17/1998

WELL/LEASE NO./PROJECT	WELL/PROJECT LOCATION	STATE	OWNER		
LANE TRUST 1-6	STEVENS	KS	SAME		
SERVICE LOCATION	CONTRACTOR	JOB PURPOSE	TICKET DATE		
LIBERAL	SWEETMAN	CEMENT PRODUCTION CASINO	11/17/1998		
ACCT. NO.	CUSTOMER AGENT	VENDOR NO.	CUSTOMER P.O. NUMBER	SHIPPED VIA	FILE NO.
54850	DARYL J. HANSON			COMPANY TRUCK	59754

ORIGINAL

DIRECT CORRESPONDENCE TO:

MCCOY PETROLEUM CO
ATTN: KELTH MCCOY
3017 N. CYPRESS
WICHITA, KS 67228-4009

P O BOX 1578
LIBERAL, KS 67901

REFERENCE NO.	DESCRIPTION	QUANTITY	UM	UNIT PRICE	AMOUNT
	DISCOUNT-(BID)	27.0 %			69.45-
509-968	SALT	1576 LB		.15	236.40
	DISCOUNT-(BID)	27.0 %			63.82-
018-315	MUD FLUSH	420 GAL		.65	273.00
	DISCOUNT-(BID)	27.0 %			73.71-
320-806-71415	BASKET-CMT-4 1/2 CSO X 18"OD-	1 EA		97.00	97.00
	DISCOUNT-(BID)	25.0 %			24.25-
019-241	CASING SWIVEL W/O WALL CLEANER	1 JOB		185.00	185.00
	DISCOUNT-(BID)	25.0 %			46.25-
500-207	BULK SERVICE CHARGE	297 CFT		1.35	402.15
	DISCOUNT-(BID)	27.0 %			108.61-
500-306	MILEAGE-CMTG MAT DEL OR RETURN	339.1145 TMT		.95	322.16
	DISCOUNT-(BID)	27.0 %			87.01-

RELEASED

MAR 23 1998

FROM CONFIDENTIAL

INVOICE SUBTOTAL	20,217.16
DISCOUNT-(BID)	4,837.60
INVOICE BID AMOUNT	15,379.56
* KANSAS STATE SALES TAX	592.14
* LIBERAL CITY SALES TAX	112.69
* SEWARD COUNTY SALES TAX	112.69

INVOICE TOTAL - PLEASE PAY THIS AMOUNT \$16,157.08

TERMS: If Customer does not have an approved open account with Halliburton, all sums due are payable in cash at the time of performance of services or delivery of equipment, products or materials. If customer has an approved open account, invoices are payable on the twentieth day after date of invoice. Customer agrees to pay interest on any unpaid balance from the date payable until paid at the highest lawful contract rate applicable, but never to exceed 18% per annum. In the event Halliburton employs an attorney for collection of any account, Customer agrees to pay attorney fees of 20% of the unpaid account, plus all collection and court costs.