

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2125  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-175-20574-0000

API NUMBER N/A

LEASE NAME Kane Trust

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1 Old Well  
1275 Ft. from S Section Line

4005 Ft. from E Section Line

LEASE OPERATOR Elder & Vaughn Inc.

SEC. 13 TWP. 32 RGE. 33 (X) or (W)

ADDRESS P.O. BOX 18938, OKC, OK 73154

COUNTY Seward

PHONE# (405) 842-8877 OPERATORS LICENSE NO. 7457

Date Well Completed 6/11/96

Character of Well DRY

Plugging Commenced 5-2-96

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 5-3-96

The plugging proposal was approved on 5-2-96 AM 5-2-96 PM (date)

by Steve Durant & later Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? YES If not, Is well log attached? \_\_\_\_\_

Producing Formation CHASE Depth to Top 2631 Bottom 2806 T.D. 3290

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
CHASE	SALTWATER	2631	2806	8 3/8		—0
				5 1/2		—0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each s. 5 1/2 was stuck @ 150ft - Mixed 3 SX hulls & 25 SX cement to plug perf. from 2650 to 2450, displaced w/mud to 1800. Mixed 50 SX cement plug in 5 1/2 from 1800 to 1400 & displaced w/mud to 720. Mixed 25 SX cement plug in 5 1/2 from 720 to 520, mud to 40, mixed 5 SX cmt. 40 too. Mixed 10 SX cement plug down 8 3/8 & 5 1/2 annulus to press. to 500 PSI. Cut off 8 3/8 & cap 8 3/8 3ft. below G.L.  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent And Horton Plugging, Inc. License No. 31151

Address Rt. 1, Box 49 BA Tyrone, OK 73951-9731

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ELDER & VAUGHN

RECEIVED  
KANSAS CORPORATION COMMISSION

STATE OF OKLAHOMA COUNTY OF OKLAHOMA, ss.

JUN 06 1996

JACK H. VAUGHN

(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the above-described well, and matters herein contained and the log of the above-described well, the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P.O. BOX 18938, OKC, OK 73154

SUBSCRIBED AND SWORN TO before me this 5th day of JUNE, 19 96

[Signature]  
Notary Public

My Commission Expires: 1/16/98

