


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Seward County, Sec. 13 Twp. 32 S Rge. 33W E/W
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines _____

NE NE SW
Lease Owner First National Oil Co.
Lease Name Kane Well No. 1
Office Address 23 East 11th. Liberal, Kansas 67901
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above Section Plot

Gas
Date Well completed _____ 19____
Application for plugging filed 4-22- 1980
Application for plugging approved 4-25 1980
Plugging commenced 5-6 1980
Plugging completed 5-10 1980
Reason for abandonment of well or producing formation _____

Dry
If a producing well is abandoned, date of last production _____ 19____
Unknown

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 6040
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	1642	none
				5 1/2	4402	2642

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

- Spot 25 sks. of cement @ 4364 to 4200
- Spot 35 sks. of cement @ 1600 to 1500
- Spot 25 sks. of cement @ 800 to 700
- Put 10 sks. of cement @ 40 to 0

RECEIVED
COMMISSION
JUN - 9 1980

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sargents Casing Pulling Service Box 506 Liberal, Kansas 67901


STATE OF KANSAS COUNTY OF Seward, ss.
WF McKeen (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) WF McKeen
23 E. 11th Liberal KS 67901
(Address)

SUBSCRIBED AND SWORN TO before me this 6 day of June, 1980

Cheley A. Rodgers
Notary Public.

My commission expires 10/11/80



DRILLERS LOG

KANE NO. 1-

CASING RECORD:	OPERATOR: Sage drilling Co.	DESCRIPTION:
8 5/8 @ 1642	CONTRACTOR:	Ne Ne Sw
5 1/2 @ 4402	COMMENCED: 4-18-72	Section 13-32S-33W
TOTAL DEPTH:	COMPLETED: 4-30-72	Seward County, Kansas
6040		

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil and Sand	0	420	
Red Bed	420	601	
Red Bed & Gyp	601	900	
Sand	900	1060	
Red Bed and Lime	1060	1288	
Red Bed and Gyp	1288	1567	
Anhydrite	1567	1596	
Shale	1596	2357	
Shale and Lime	2357	2548	
Lime and Shale	2548	5120	
Lime	5120	5234	
Lime and Shale	5234	5916	
Lime, Shale and Sand	5916	6012	
Lime	6012	6040	

RECEIVED
 STATE CORPORATION COMMISSION
 APR 23 1980
 CONSERVATION DIVISION
 Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

Subscribed and sworn to before me this 22nd day of April 1980.

Dorothy Sargent

My commission expires: Dec. 11th. 1981

