

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2125
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 175-215180000

LEASE NAME Kane Trust

WELL NUMBER 1-13

330 Ft. from S Section Line

1155 Ft. from E Section Line

SEC. 13 TWP. 32 RGE. 33 (X) or (W)

COUNTY Seward

Date Well Completed 1/23/96

Plugging Commenced 5-6-96

Plugging Completed 5-7-96

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Elder & Vaughn, Inc.

ADDRESS P. O. Box 18938, OKC, OK 73154

PHONE# (405) 842-8877 OPERATORS LICENSE NO. 7457

Character of Well DRY

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5-6-96 (date)

by Steve Phifer (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached? _____

Producing Formation DRY HOLE Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
CHASE	SALTWATER	2806	14	8 5/8	1672	0
CHASE	SALTWATER	2790	96	5 1/2	3257	2207
CHASE	SALTWATER	2742	50			
CHASE	SALTWATER	2692	2700			
CHASE	SALTWATER	2623	66			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from _____ feet to _____ feet each s
Mixed 3 sx hulls to 25 sx cmt. to plug perfs from 2631 to 2431. Shot 5 1/2 loose @ 2207. Pulled to 1700. Circ hole w/mud to mixed 50 sx cmt plug from 1700 to 1550. Pulled to 700 to mixed 25 sx cmt plug from 700 to 600. Pulled to 40. Mixed 10 sx cmt. plug from 40 to 0. Cut off & capped 8 3/4 3 ft. below ground level.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent And Horton Plugging, Inc. License No. 31151

Address Rt. 1, Box 49 BA Tyrone, OK 73951-9731

RECEIVED
KANSAS CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ELDER & VAUGHN

STATE OF OKLAHOMA COUNTY OF OKLAHOMA, ss.

JUN 06 1996

JACK H. VUAGHN (Employee of Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P.O. BOX 18938, OKC, OK 73154

SUBSCRIBED AND SWORN TO before me this 5th day of JUNE, 19 96

[Signature]
Notary Public

My Commission Expires: 1/16/98

