

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 175-20-834- <sup>0000</sup>

LEASE NAME Franz

WELL NUMBER #1

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

500 Ft. from S Section Line

4780 Ft. from E Section Line

SEC. 16 TWP. 32 RGE. 33 (E) or (W)

COUNTY Seward

LEASE OPERATOR Hugoton Energy Corp.

ADDRESS 229 E. Williams, Ste. 500, Wichita, Ks. 67202

PHONE# (316) 262-1522 OPERATORS LICENSE NO. 3871

Date Well Completed 3-29-1985

Character of Well oil

Plugging Commenced 10-8-1991

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10-11-1991

The plugging proposal was approved on 10-6-1991 (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation Chester Depth to Top 5622 Bottom 5788 T.D. 6003'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
Formation	Content	From	To	Size	Put in	Pulled out
Surface				8 5/8"	1615'	0'
Production				5 1/2"	6003	2760'

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 17 1991  
Wichita Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pump 2 Skis. Halls & 25 Skis. cement to 5400' - Pressured to 700 lbs.  
Pump 50 Skis. cement at 2700' to 2550' - Pump 50 Skis. cement 1600' to 1450'  
Pump 40 Skis. cement 700' to 580' -- Put bridge and 10 Skis. 40' to 3'  
Cut off 8 5/8", 3' below ground level and cap  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Midwest Casing Pulling Service License No. 6497

Address Box F, Sublette, Ks. 67877

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Hugoton Energy Corp.

STATE OF KANSAS COUNTY OF HASKELL, ss.

I, Edgar J. Eves (Employee of Operator) or (~~Operator~~) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

**SONDRA L. EVES**  
NOTARY PUBLIC - STATE OF KANSAS  
My Appt. Exp. 12-6-92

(Signature) [Signature]

(Address) Box F, Sublette, Ks. 67877

SUBSCRIBED AND SWORN TO before me this 15th day of Oct., 1991

[Signature]  
Notary Public

My Commission Expires: 12-6-92