

API NUMBER 15-175-21302-0001

LEASE NAME Longcor B

WELL NUMBER 2

1980 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 18 TWP. 32 RGE. 33 (W) or (W)

COUNTY Seward

Date Well Completed 5-7-1994

Plugging Commenced 3-29-2000

Plugging Completed 3-29-2000

APR 18 2000

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

CONSERVATION DIVISION  
 Wichita, Kansas

LEASE OPERATOR Oxy USA, Inc.

ADDRESS 1701 N Kansas Liberal KS 67905

PHONE# (316) 629 4200 OPERATORS LICENSE NO. 5447

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3-29-2000 (date)

by Gary Winters (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation Chase Depth to Top 2431 Bottom 2542 T.D. 5800

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				<u>8 5/8</u>	<u>1530</u>	<u>-</u>
				<u>5 1/2</u>	<u>2790</u>	<u>-</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other p were used, state the character of same and depth placed, from feet to feet each :  
Mixed 4 SX hulls to 25 SX to plug perfs from 2431 to 2231. Load w/mud to 1630. 25 SX 1630 to 1430 Mud to 550 65 SX 550 to 0 in 5 1/2  
Mixed 10 SX plug down annulus from 60 to 0 to pres. up to 500 PSI

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargents Casing Pulling Service License No. 6547

Address: Box 506 Liberal KS 67905

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Oxy USA Inc.

STATE OF Kansas COUNTY OF Seward, ss.


Kenny L. Andrews (Employee of Operator) or (Operator above-described well, being first duly sworn on oath, says: That I have knowledge of the fa. statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Kenny Andrews

(Address) PO Box 2528 Liberal, KS. 67905

SUBSCRIBED AND SWORN TO before me this 12th day of April, 2000

Anita Peterson  
 Notary Public



Commission Expires: Oct 1, 2001