


15-175-00263-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Seward County. Sec. 19 Twp. 32S Rge. 33 (E) (W)  
Location as "NE/CNW/SW" or footage from lines G/ SE/4  
Lease Owner Graham-Michaelis Drilling Company  
Lease Name Griffith Well No. 1  
Office Address 211 North Broadway  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed December 22, 19 58  
Application for plugging filed January 10, 19 59  
Application for plugging approved January 19, 19 59  
Plugging commenced February 23, 19 59  
Plugging completed February 25, 19 59  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production - 19 -  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Merl Rives, Garden City, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 2,695 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Sand, Clay, Gyp & Red Bed		0'	548'	8-5/8"	548'	0'
Red Bed, Gyp, Sand, Shale, Anhydrite, Lime, & Dolomite		548'	2,695'	5 1/2"	2,691'	1,310'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mudded hole to 545' set 10' rock bridge, mixed and dumped 20 sacks cement with dump bailer. Mud to 40', set 10' rock bridge, Dumped 10 sacks cement to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 12 1959  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Company, Inc.  
Address P. O. Box 364, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
O. W. Woodland (employee of owner) or ~~(owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) O. W. Woodland

211 North Broadway, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of March, 19 59

My commission expires 1-7-61

V. D. Grier  
Notary Public.

PLUGGING  
FILE SEC. 19 T. 32 R. 33W  
BOOK PAGE 11 LINE 2

G R I F F I T H 61

WELL RECORD

LOCATION: Sec. 19-T32S-R33W Commenced: 12/16/58  
Seward County, Kansas Completed: 12/22/58  
(Rotary)

OPERATOR: Graham-Michaelis Drilling Company  
211 North Broadway  
Wichita 2, Kansas

CONTRACTOR: Graham-Michaelis Drilling Company  
211 North Broadway  
Wichita 2, Kansas

CASING RECORD: 8-5/8" 2548' w/300 sx comm w/41 gal gal, 2% cc  
& 1/4# Floccal per sack  
8-1/2" 2691' w/300 sx comm. cement

LOG

Sand, Clay & Gyp	0 - 405
Gyp & Red Bed	405 - 550
Red Bed, Gyp & Sand	550 - 1180
Sand, Red Bed, Gyp & Shale	1180 - 1880
Red Bed, Gyp & Shale	1880 - 2100
Shale & Anhy	2100 - 2358
Shale, Lime & Anhy	2358 - 2465
Lime & Shale	2465 - 2530
Shale & Anhy	2530 - 2590
Shale & Dolomite	2590 - 2690

Rotary Total Depth - 2695'

The undersigned, GRAHAM-MICHAELIS DRILLING COMPANY, hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above well as reflected by the Daily Drilling Report.

GRAHAM-MICHAELIS DRILLING COMPANY

Original Signed by:  
JACK L. YINGER  
By \_\_\_\_\_  
Geologist

RECEIVED  
STATE CORPORATION COMMISSION

JAN 17 1959  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC 19 T 32 R 33W  
BOOK PAGE 11 LINE 2