

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-175-00266-0000  
API NUMBER 1-30-1950

RECEIVED

MAR 19 1990

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE NAME Mercer

WELL NUMBER 2

1650 Ft. from N Section Line

1320 Ft. from W Section Line

SEC. 21 TWP. 32S RGE. 33W (E) or (W)

COUNTY: Seward

Date Well Completed 1-30-50

Plugging Commenced 2-27-90

Plugging Completed 3-1-90

LEASE OPERATOR CABOT-OKC  
Cabot Petroleum Corporation

ADDRESS 9400 N. Broadway Suite 608 Okla, City, Okla.

PHONE (405) 478-6500 OPERATORS LICENSE NO. 6120

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Glenn Barlow - District 1

Is ACO-1 filed? No If not, is well log attached? No ACO-1 or Logs available

Producing Formation Chase Group Depth to Top 2483 Bottom 2577 T.D. 2633

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Herrington	Gas	0	390	10 3/4	390	0
Krider	Gas	0	2483	7	2483	800
Winfield	Gas	2443	2577	5 1/2	134	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pump 50 sks. of cement & 2 sks. of hulls @ 2430 to 2100 tag plug @ 1945  
Pump 50 sks of cement from 1800 to 1550 Pump 50 sks. of cement from 800 to 700  
Pump 50 sks. of cement from 410 to 310  
Put 15 sks. of cement from 40 to 0 Cut off & cap 10 3/4 4' below ground level  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address P.O. Box 506 Liberal, Kansas 67905-0506

STATE OF Kansas COUNTY OF Seward, ss.

Jan Sexton (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jan Sexton

(Address) 9400 N. Broadway, Ste 608, OKC, OK

Subscribed and sworn to before me this 22 day of March, 1990

Robert E. Mitchell  
Notary Public

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 22 1990  
CONSERVATION DIVISION  
Wichita, Kansas

Commission Expires: November 8, 1992

Form CP-4  
Revised 08-84