

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-175-20447-2000

LEASE NAME Betty Lemert B

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 2

660 Ft. from S Section Line

660 Ft. from E Section Line

LEASE OPERATOR Amoco Production Co.

SEC. 22 TWP. 32 SRGE. 33 KE or (W)

ADDRESS P. O. Box 432

COUNTY Seward

PHONE#(316) 624-6241 OPERATORS LICENSE NO. 5952

Date Well Completed 3-4-80

Character of Well Oil

Plugging Commenced 7-6-87

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 7-8-87

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City, KS

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Morrow Depth to Top 5438 Bottom 5448 T.D. 6000

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Morrow	Oil	5438	5448	8-5/8 5-1/2	1613 6000	0 (Surface) 1646 (Production)

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Set CIBP @5310 w/2 sxs cmt-mud to 1640' - Pump 50 sxs. Cmt 1640' to 1540' Mud to 800'
 Pump 35 sxs cmt 800' to 700' - Mud 700' to 40' Put bridge & 10 sxs cmt 40' to 5' - Cut off
 8-5/8 5' below ground level and cap

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Midwest Casing Pulling Service License No. 6497

Address Box F. Sublette, KS

STATE OF Kansas COUNTY OF Haskell, ss.

R. L. Hiatt (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. L. Hiatt

(Address) P. O. Box 432 Liberal, KS 67901

SUBSCRIBED AND SWORN TO before me this 20th day of July, 19 87

STATE OF KANSAS V. K. Bruce V. K. Bruce
 Notary Public

Appointment Expires: 4-28-89

JUL 22 1987

