

STATE OF KANSAS
STATE CORPORATION COMMISSION
Finney State Office Building
130 South Market, Rm 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-129-21339 - 0000

LEASE NAME BOEKHAUS TRUST "A"

WELL NUMBER 1

1250 Ft. from S Section Line

2250 Ft. from E Section Line

SEC. 5 TWP. 32 RGE 41 (E) or W

COUNTY MORTON

Date Well Completed 01-09-95

Plugging Commenced 11-28-95

Plugging Completed 11-28-95

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-27-95 (date)

by GARY WINTERS (KCC District Agent's Name).

Is AC0-1 filed? YES If not, is well log attached? _____

Producing Formation NONE Depth to Top _____ Bottom _____ T.D. 2460

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

ICASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	703'	NONE
				5-1/2"	2417'	NONE

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

MIRU PLUGGERS. PMP 15 SXS HULLS & 25 SXS CMT DWN CSG FROM 1978-2178. DISPLACE W/27 BM FOLLOWED BY 90 SX CMT PLUG FROM 750-0. PUMP 10 SX DOWN 8-5/8X5-1/2 ANN. PRESS TO 500 PSI. CUT 8 5/8" & 5-1/2" OFF 3 FEET BELOW GL. CAP & PERMANENTLY INSCRIBE WELL NAME AND DATE PLUGGED ON CAP. RDMO PLUGGERS. WITNESSED BY KCC REP GARY WINTERS.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor: SARGENT & HORTON PLUGGING License No. 3115
Address RT. 1, BOX 49BA, TYRONE, OKLAHOMA 73951-9731 **RECEIVED**
STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION DEC - 6 1995

STATE OF KANSAS COUNTY OF SEWARD CONSERVATION DIVISION
Wichita, Kansas

DAVID W. KAPPLE (Employee of Operator) or (xxxxxxx) of above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) David Kapple

(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 4th day of December, 1995

Freda L. Hinz
Notary Public

My Commission Expires: _____

