


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Morton County, Sec. 5 Twp. 32 Rge. 41W (E) (W)

Location as "NE/CNW/SW" or footage from lines SE/4
Lease Owner D. J. Stone
Lease Name Boekhaus Well No. 1
Office Address 2010 34th St., Lubbock, Texas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed 10/31 19 63
Application for plugging filed 10/31 verbally 19 63
Application for plugging approved 10/31 verbally 19 63
Plugging commenced 10/31 19 63
Plugging completed 10/31 19 63
Reason for abandonment of well or producing formation Dry hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh E. Scott
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5415' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	1514'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole w/mud, spot 35 sx common cmt. @ 700'.
Mud up to 40', 15 sx to bottom of collar, 3 1/2' below ground level.

RECEIVED
STATE CORPORATION COMMISSION

NOV 6 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____
Address _____

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
Donald L. Roberts (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Russell State Bank Bldg., Russell, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of November, 1963
[Signature]
Notary Public.

My commission expires: 6/17/66



15-129-10158-0000

D. J. STONE
BOEKHAUS #1

SE Section 5-32-41W
Morton County, Kansas

R.T.D. 5415
Commenced 10/16/63
Completed 10/31/63

CONTRACTOR: Roberts Drilling Co.
Set 8 5/8" @ 1514' w/600 sx cmt

Surface hole	662'
Shale & Sand	1010
Anhydrite & Gyps. streaks	1119
Sand	1240
Sand & Red Bed	1500
Anhydrite	1523
Sand, Shale & Shells	1740
Red Bed & Shale	2205
Shale & Lime	2579
Lime, Shale & Chert	2710
Lime	2918
Lime & Chalk	3060
Lime	4305
Lime & Shale	5068
Lime	5086
Shale	5245
Sand	5313
Sand, Lime & Shale	5375
Lime & Shale	5390
Lime	5415

RECEIVED
STATE CORPORATION COMMISSION
NOV 6 1963
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
RUSSELL COUNTY) SS

I hereby certify that the above information is correct to the best of my knowledge.

ROBERTS DRILLING CO.

By [Signature]

Subscribed and sworn to before me this 5th day of November, 1963.

[Signature]
Notary Public

My Commission Expires 6/17/66