

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-129-21096-  
0000

LEASE NAME Harrison

WELL NUMBER 1-9

-TYPE OR PRINT -  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

3300 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 9 TWP. 32 RGE. 40 (E) or (W)

COUNTY Morton

Date Well Completed 9-20-91

Plugging Commenced 9-23-91

Plugging Completed 9-23-91

LEASE OPERATOR Trans Pacific Oil Corporation

ADDRESS 1000 One Main Place Wichita, Kansas

PHONE# (316) 262-3596 OPERATORS LICENSE NO. 9408

Character of Well D & D

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-23-91 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? \_\_\_\_\_

Producing Formation N/A Depth to Top \_\_\_\_\_ Bottom T.D. 5700

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED

STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out

NOV 12 1991

REGIONAL DIVISION  
WICHITA, KANSAS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from     feet to     feet each set.

SEE ATTACHED

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Trans Pac Drilling License No. 5841

Address 1000 One Main Place Wichita, Kansas 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Trans Pacific Oil Corporation

STATE OF Kansas COUNTY OF Sedgwick, ss.

Alan D. Banta (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Alan D. Banta

(Address) 1000 One Main Place



SUBSCRIBED AND SWORN TO before me this 1st day of November, 19 91

Sondra J. Boyd  
Sondra J. Boyd Notary Public

My Commission Expires: May 13, 1995

RECEIVED  
STATE CORPORATION COMMISSION

NOV 12 1991

CONSERVATION  
Wichita, Kansas

DRILLER'S WELL LOG

Harrison #1-9  
C SE NW 9-32S-40W  
Morton County, Kansas

Trans Pacific Oil Corporation  
Commenced: September 9, 1991  
Completed: September 20, 1991

0'	-	710'	Red Bed
710'	-	1700'	Red Bed
1700'	-	2520'	Lime
2520'	-	3290'	Lime & Shale
3290'	-	3825'	Shale
3825'	-	4320'	Shale & Lime
4320'	-	4810'	Shale & Lime
4810'	-	4990'	Lime & Shale
4990'	-	5269'	Shale
5269'	-	5375'	Shale
5375'	-	5595'	Shale & Lime
5595'	-	5700'	Shale & Lime
	-	5700'	RTD

Surface Casing: Set 8 5/8" x 24#  
new @ 1678', set @ 1692' w/615 sacks  
35/65 pozmix 6% D-20, 2% cc, 4 sacks  
D-29, 150 sacks "C" 2% cc, 1/4 sack  
D-29.

Plugging: Cement with 60/40 pozmix  
6% gel, set plug @ 2889' to 1720'  
800-40' w/100 sacks on 1st plug,  
50 sacks on 2nd plug, 50 sacks on 3rd  
plug, 10 sacks on 4th plug, 15 sacks  
Rat Hole and 10 sacks Mouse Hole.

AFFIDAVIT

STATE OF KANSAS        )  
                                  ) SS.  
COUNTY OF SEDGWICK )

Alan D. Banta of lawful age does swear and state  
that the facts and statement herein are true to the best of his knowledge.

*Alan D. Banta*

Subscribed and sworn to me this 8th day of November, 1991.

My commission expires: May 13, 1995

*Sondra J. Boyd*  
Sondra J. Boyd NOTARY PUBLIC

