

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

NORTH

	X		

Locate well correctly on above Section Plat

Morton County, Sec. 12 Twp. 32S Rge. 40 ~~XXX~~ X (W)
 Location as "NE/CNW/SW" or footage from lines. C SE NW
 Lease Owner. Cities Service Oil Company
 Lease Name. French "A" Well No. 2
 Office Address. Box 1228, Guymon, Oklahoma
 Character of Well (completed as Oil, Gas or Dry Hole) Gas
 Date well completed. 8-25 1960
 Application for plugging filed. 2-24 1970
 Application for plugging approved. 2-25 1970
 Plugging commenced. 3-18 1970
 Plugging completed. 3-21 1970
 Reason for abandonment of well or producing formation. Uneconomical to produce

If a producing well is abandoned, date of last production. 2-20 1970
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well. Mr. E. Eves, Sublette, Kansas
 Producing formation. Morrow S-3 Depth to top. 5672 Bottom. 5804 Total Depth of Well. 6176 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Morrow S-3	Gas	5672	5804	8 5/8	1706	None
				4 1/2	5870	2325

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Cement plugs were spotted as follows: spotted 75 sacks cement from 5798' to 4789', mudded hole from 4789' to 1600', spotted 40 sacks cement from 1600' to 1495', mudded hole from 1495' to 35', spotted 10 sacks cement from 35' to 5'. Cut off 8 5/8" casing 5 feet below ground level and welded on steel cap with well name and date on cap.

RECEIVED
STATE CORPORATION COMMISSION
APR 1 - 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor. Daco Well Service
 Address. 1700 S. Main, Borger, Texas

STATE OF OKLAHOMA, COUNTY OF TEXAS, ss.
 H. E. Massey (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H. E. Massey *H. E. Massey*
 Dist. Manager, Box 1228, Guymon, Oklahoma
 (Address)

SUBSCRIBED AND SWORN to before me this 30th day of March, 1970

Dan B. Codner
 Dan B. Codner Notary Public.

My commission expires 10-21-73

DRILLER'S LOG
 French "A" #2
 Sec. 12-32S-40W
 Morton Co., Kansas

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 25 1970
 CONSERVATION DIVISION
 Wichita, Kansas

Gyp	0 - 43
Gyp and Shale	43 - 820
Anhydrite and Red Bed	820 - 1380
Anhydrite and Shale	1380 - 1707
Anhydrite	1707 - 1790
Anhydrite and Red Bed	1790 - 2240
Anhydrite and Shale	2240 - 2480
Lime and Shale	2480 - 2655
Lime	2655 - 2775
Lime & Shale	2775 - 2870
Lime	2870 - 2930
Lime & Shale	2930 - 3030
Lime	3030 - 3270
Lime & Shale	3270 - 3419
Lime	3419 - 3857
Lime & Shale	3857 - 3917
Lime	3917 - 5205
Lime & Shale	5205 - 5515
Sand	5515 - 5531
Sand & Shale	5531 - 5548
Shale	5548 - 5691
Sand & Shale	5691 - 5698
Lime	5698 - 5730
Shale & Sand	5730 - 5862
Shale & Lime	5862 - 6039
Lime	6039 - 6176
T.D.	6176