

STATE OF KANSAS
STATE CORPORATION COMMISSION
209 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

20451
API NUMBER 15-129-21451-0000

LEASE NAME Fortenbaugh Gas Unit

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

1980 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 19 TWP. 32S RGE. 40 (E) or (W)

COUNTY Morton

Date Well Completed 2-27-81

Plugging Commenced 9-11-95

Plugging Completed 9-11-95

LEASE OPERATOR Amoco Production Company

ADDRESS PO Box 800 Room 924 Denver, CO 8021

PHONE# (303) 830-5323 OPERATORS LICENSE NO. 5952

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on September 1, 1995 (date)

by Steve Durant (KCC District Agent's Name).

Is ACO-1 filled? yes If not, Is well log attached? _____

Producing Formation Council Grove Depth to Top 2554' Bottom 2663' T.D. 2800'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface			8 5/8"	682'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
See attached

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No.

Address

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Amoco Production Company

STATE OF Colorado COUNTY OF Denver, ss.

Susan R. Potts (Employee of Operator) or (Operator) of
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts,
statements, and matters herein contained and the log of the above-described well as filed that
the same are true and correct, so help me God.

(Signature) Susan R. Potts

(Address) PO Box 800 Room 924 Denver, CO 80201

SUBSCRIBED AND SWORN TO before me this 12th day of October, 1995

Susan Callahan
Notary Public
My Commission Expires: August 2, 1998

Date: 8/14/1995

Type of Operation: Plug & Abandonment

Lease and Well Number: Fortenbaugh Gas Unit No. 19-1

Field: Hugoton

Formation: Council Grove

Location: Sec 19- T32S - R40W

TD: 2800' **PBTD:** 2761'

Surface Csg: 8 5/8" 20 ppf set @ 682', cmt w/ 350 sx circulated

Production Csg: 5 1/2" 14 ppf set @ 2799', cmt w/ 550 sx circulated

Purpose: TO PxA the Subject Well

Procedure:

1- MIRU.

2- Set a cement plug to the surface w/ 300 sx of 60/40 POZ, 14.4 ppg, Class 'C' cement.
Add 2 sx of cotton seed hulls to the first 10 sx of cement.

3- Check the backside and have 50 additional sx of cement on location.

4- Cut off csg 3' below the ground and weld on steel cap w/ lease identification.

5- Restore the location.

Note: Please contact the KCC 48 hours prior to the scheduled date.

Procedure reviewed w/ KCC representative Steve Middleton on 8/14/95.

Prepared By: Sonia K. Vahedian
Petroleum Engineer

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 13 1995

CONSERVATION DIVISION
WICHITA, KS