

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-129-00075-0000

LEASE NAME Bonham G.U. B

WELL NUMBER 1

3300 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 24 TWP. 32S RGE. 40 (E) or (W)

COUNTY Morton

Date Well Completed 12-24-60

Plugging Commenced 8-29-86

Plugging Completed 9-5-86

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Amoco Production Company

ADDRESS P. O. Box 432 Liberal, KS 67901

PHONE# (316) 624-6241 OPERATORS LICENSE NO. 5952

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Morrow Depth to Top 5405 Bottom 5870 T.D. 6000

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing	Wtr	4338	4509	8-5/8	705'	
Cherokee	Wtr	4509	5405	4-1/2	5964'	1030'
Morrow	Gas	5405	5870			
Chester	Wtr	5870	6000			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

CIBP set at 5690' x Capped x 2 sxs cmt x Shot off 4-1/2" csg @ 2800'; 1400'; Would not pull x shot off @ 1030' x csg came free x pull 1 It 4-1/2" csg x lay down x pump 50 sx cmt plug @ 4-1/2" csg stub @ 1030' x pump 75 sx cmt plug x TOH x 4-1/2" csg x pump from 40' to 5' Cut off 8-5/8" csg 5' below ground level x capped.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Midwest Casing License No. _____


Address Box F Sublette, KS 67877

STATE OF Kansas COUNTY OF Seward, ss.

Larry L. Smith (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Larry L. Smith

(Address) P. O. Box 432 Liberal, KS 67901



SUBSCRIBED AND SWORN TO before me this 16th day of September, 19 86

V. K. Bruce
 Notary Public

My Commission Expires: 4-28-89

SEP 18 1986