

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67702

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-129-216040000

Lease Name Speakman

WELL NUMBER 1-126

4,850 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 26 TWP. 32S RGE. 40W (E) or (W)

COUNTY Morton

Date well completed 7/4/00

Plugging Commenced 7/6/00

Plugging completed 7/6/00

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Pioneer Oil Company

Address RR 4 Box 142B Lawrenceville, IL 62439

Phone (618) 943-5314 OPERATORS LICENSE NO. 32468

Character of Well D&A

Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7/1/00 (date)

by Steve Durrant (KCC District Agent's Name).

Is ACO-1 filed? yes If not, IS well log attached? yes (with ACO-1)

Producing Formation Dry hole Depth to Top _____ Bottom _____ T.D. 6,183 ft

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				<u>2 5/8"</u>	<u>11033</u>	<u>0</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set RIH w/ drill pipe to 3000'. Spot 100 sk plug at 3000' to 2550'. Pull DP to 1530', spot 50 sk plug from 1530' to 1308'. Pull DP to 690', spot 25 sk from 690' to 580'. Pull DP to 40', spot 10 sk from 40' to 0'. POH w/ DP. Plug rathole w/ 15 sk. Plug mousehole w/ 10 sk.

Total cement used 210 sk 60/40 pozmix w/ 6% gel.

RECEIVED
STATE CORPORATION COMMISSION

Name of Plugging Contractor Norseman Drilling License No. 3779

Address 200 E. First St, Suite 307 Wichita, KS 67202

AUG 21 2000

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Pioneer Oil Company

CONSERVATION DIVISION
Wichita, Kansas

STATE OF Indiana COUNTY OF Warrick '33.

George A. Payne (Employee of operator) or (Operator) of the of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the that the same are true and correct, so help me God. (Signature) George A. Payne

(Address) 7588 Marywood Drive Newburgh, IN 47630

Subscribed and sworn to before me this 16th day of August, 19 00

Lisa R. Herie
Notary Public

My commission expires: March 29, 2008

