


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

## WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Morton County, Sec. 30 Twp. 32S Rge. 10 (X) (W)  
Location as "NE/CNW/SW" or footage from lines G SW/4  
Lease Owner J. M. Huber Corporation  
Lease Name Krey Well No. 1  
Office Address Box 978, Liberal, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Gas  
Date well completed March 28 19 64  
Application for plugging filed October 30 19 64  
Application for plugging approved October 30 19 64  
Plugging commenced October 30 19 64  
Plugging completed Nov. 2 19 64  
Reason for abandonment of well or producing formation Depleted  
until uneconomical  
If a producing well is abandoned, date of last production Sept. or Oct. 19 64  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott  
Producing formation \* see below Depth to top 2266 Bottom 2412 Total Depth of Well 2412 Feet  
Show depth and thickness of all water, oil and gas formations. \*Winfield

## OIL, GAS OR WATER RECORDS

Krider  
Herrington

## CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>Winfield</u>	<u>Gas</u>	<u>2332</u>	<u>2358</u>	<u>8 5/8"</u>	<u>475</u>	<u>0</u>
<u>Krider</u>	<u>Gas</u>	<u>2288</u>	<u>2300</u>	<u>5 1/2"</u>	<u>2412</u>	<u>1230</u>
<u>Herrington</u>	<u>Gas</u>	<u>2264</u>	<u>2273</u>			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mix 20 sacks & pumped in wellStopped with top @ 2150' - Mud from 2150' to 500'35 sacks 500' to 400'Mud 400' to 15'15 sacks 15' to 0'Welded plate on top.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 6 1964

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sargents Casing Pulling  
Address Liberal, Kansas

STATE OF Kansas, COUNTY OF Seward, ss.  
Harold Jones (employee of owner) or (owner) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Harold Jones  
Box 978, Liberal, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 4 day of November, 19 64Pauline K. Wilson

Notary Public.

My commission expires My Commission Expires September 4, 1963

## W E L L L O G

Well Name: Krey #1  
 Well Location: C SW/4 Sec 30, T32S R40W  
 Morton County, Kansas  
 Well Owner: J. M. Huber Corporation  
 Drilling Commenced: March 6, 1954  
 Drilling Completed: March 10, 1954  
 Well Completed: March 28, 1954  
 Total Depth: 2424

Formation	Depth
Sand, Clay	0 - 350
Red Bed, Sand	350 - 440
Red Bed	440 - 517
Clay, Sand	517 - 640
Red Bed, Sand	640 - 720
Red Bed, Gyp	720 - 1160
Anhydrite	1160 - 1200
Sand, Red Bed, Shells	1200 - 1760
Shale & Gyp	1760 - 2004
Shale, Shells, Lime Streaks	2004 - 2258
Anhydrite & Shale	2258 - 2325
Sand	2325 - 2330
Shale streaks & Lime	2330 - 2412
Lime	2412 - 2424

RECEIVED  
 STATE CORPORATION COMMISSION  
 NOV 6 1964  
 CONSERVATION DIVISION  
 Wichita, Kansas

State of Kansas, County of Seward:

I, Harold Jones, employee of the owner of the above described well, being first duly sworn on oath, says: That I have knowledge of facts, statements and matters herein contained and the log of the above described well as filed and that the same are true and correct.

Harold Jones

Subscribed and sworn to before me this 30 day of October, 1964.

Pauline K. Wilson

My commission expires My Commission Expires September 4, 1968