

API NUMBER 15-175-21243-0000

LEASE NAME Boyer C

WELL NUMBER 3

660 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 35 TWP. 32S RGE. 34 ^{XX} (S) or (W)

COUNTY Seward

Date Well Completed 3/24/92

Plugging Commenced 3/24/92

Plugging Completed 3/24/92

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR OXY USA Inc.

ADDRESS P. O. Box 26100, Oklahoma City, OK 73126-0100

PHONE#(405) 949-4268 OPERATORS LICENSE NO. 5447

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on March 24, 1992 (date)

by Mr. Steve Durrant (KCC District Agent's Name).

Is ACO-1 filled? yes If not, Is well log attached? yes

Producing Formation None (Dry Hole) Depth to Top — Bottom — T.D. 5836'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
MORROW	Dry			8 5/8"	1689'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
 Cmt'd 1st plug w/100 sx 60/40 Cl. H. w/6% total gel. Bottom of plug @ 3350'. Top of plug @ 3002'. Pmpd 2nd plug w/50 sx 60/40 Cl. H. w/6% gel. Bottom of plug @ 1710'. Top of plug @ 1640'. Pmpd 3rd plug w/30sx 60/40 Cl. H. w/6% gel. Bottom of plug @ 690'. Top of plug @ 561'. Pmpd 4th plug w/ 10 sx 60/40 Cl. H. w/6% gel. Bottom of plug @ 40'. Top of plug @ surface. 15 sx cmt in (If additional description is necessary, use BACK of this form.)

rat hole & 10 sx cmt in mouse hole. State witness: Mr. Steve Durrant
 Name of Plugging Contractor Cheyenne Drilling Company License No. 5382'

Address Liberal, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA Inc.

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

VIC TUMLINSON (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 26100, OKC, OK 73126-0100

SUBSCRIBED AND SWORN TO before me this 27th day of March, 19 92

[Signature]
 Notary Public

My Commission Expires: 8/19/95