

LEASE NAME C.L. Rexroad

WELL NUMBER 1

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div. office within 30 days.

SE NE NEft. from S Section Line
 Ft. from E Section Line

LEASE OPERATOR Bentley & Laing

SEC. 26 TWP 33S RGE 29W (E) or (W)

ADDRESS P.O. Box 294 Wichita Falls, Texas 76307

COUNTY Meade

PHONE (817) 723-5001 OPERATORS LICENSE NO. 9183

Date Well Completed 03/31/59

Character of Well GAS

Plugging Commenced 1-9-91

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 1-14-91

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Glenn Barlow

Is ACO-1 filed? If not, is well log attached?

Producing Formation Morrow Sand Depth to Top 5676 Bottom 5700 T.D. 5776

Show depth and thickness of all water, oil and gas formations.

RECEIVED
 STATE CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Morrow	Gas	5676	5700	9 5/8	1540	0
				5 1/2	5774	2600

FEB 25 1991
 CONSERVATION DIVISION
 WICHITA, KANSAS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

- Pump 1 sks. of hulls & 25 sks. of cement from 5700 to 5500
 - Pump 50 sks. of cement from 1570 to 1470
 - Pump 50 sks. of cement from 700 to 600
 - Put 15 sks. of cement from 40 to 0 Cut off & cap 9 5/8 3' below ground level
- (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address P.O. Box 506 Liberal, Kansas 67905-0506

STATE OF Kansas COUNTY OF Seward, ss.

Doyle Bentley (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Doyle Bentley

(Address) P.O. Box 294, Wichita Falls, TX 76307

SUBSCRIBED AND SWORN TO before me this 22 day of February, 19 91

Notary Public

My Commission Expires: 07/18/94

