

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-119-20,627-0000

LEASE NAME Bender

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1

3300 Ft. from N Section Line

1980 Ft. from E Section Line

SEC. 27 TWP. 33S RGE. 29 ~~XX~~ or (W)

COUNTY Meade

Date Well Completed 9-19-83

Plugging Commenced 9-17-87

Plugging Completed 9-21-87

LEASE OPERATOR Deck Oil Co.

ADDRESS 2300 One Williams Center, Tulsa, Oklahoma 74172

PHONE# (918) 583-1181 OPERATORS LICENSE NO. 6731

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Morrow Depth to Top 5,716' Bottom 5,790' T.D. 5,950'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Morrow</u>	<u>Gas</u>	<u>5,790'</u>	<u>5,716'</u>	<u>8-5/8"</u>	<u>1,414'</u>	<u>None</u>
				<u>4-1/2"</u>	<u>5,950'</u>	<u>2,721'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Pump 2 sacks of hulls and 25 sacks of cement from 5,785'-5,500'.

Pump 50 sacks of cement from 1,444'-1,344'.

Pump 25 sacks of cement at 675'. Put 10 sacks of cement from 40'-0'.

Cut off casing and cap 8-5/8" casing three feet below ground level.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address Box 506, Liberal, Kansas 67905-0506

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Dennis Eidson, Assistant Production Mgr. for DECK OIL CO (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Dennis Eidson

(Address) 2300 One Williams Center, Tulsa, OK 74172

SUBSCRIBED AND SWORN TO before me this 9 day of October, 19 87

My Commission Expires: July 24, 1988

OCT 13 1987

Form CP-4  
Revised 08-84  
CONSERVATION DIVISION  
Wichita, Kansas

DRILLERS LOG

BENDER NO. 1

CASING RECORD:	OPERATOR:	Deck Oil Company	DESCRIPTION:
8-5/8" set @ 1414' w/750 sax cement	CONTRACTOR:	Sage Drilling Co., Inc.	Sec. 27-33S-29W Meade Co., Kansas
TOTAL DEPTH:	COMMENCED:	August 9, 1983	
5950'	COMPLETED:	August 24, 1983	


<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Red Bed	0	925	
Red Bed & Sand	925	1515	
Red Bed & Anhydrite	1515	1841	
Anhydrite	1841	2186	
Shale	2186	3585	
Shale & Lime	3585	4020	
Lime & Shale	4020	4426	
Shale & Lime	4426	4620	
Lime & Shale	4620	5237	
Shale & Lime	5237	5325	
Lime & Shale	5325	5472	
Shale & Lime	5472	5682	
Lime & Shale	5682	5775	DST#1 & 2.
Shale & Lime	5775	5865	DST#3.
Lime & Shale	5865	5950	Logged Hole. 4 1/2" set @ 5950' w/120 sax cement.

I certify that this is a true and correct copy of the log on the above captioned well to the best of my knowledge.

SAGE DRILLING CO., INC.

By John R. Bartholomew  
John R. Bartholomew

Subscribed and sworn to before me this 30th day of August, 1983.



RECEIVED  
STATE CORPORATION COMMISSION

SEP 16 1987

CONSERVATION DIVISION

Lynne A. Pringle  
Lynne A. Pringle, Notary Public