

15-119-10003-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Meade County, Sec. 29 Twp. 33S Rge. 29 ~~W~~ (W)

Location as "NE/CNW/SW" or footage from lines C NW NW

Lease Owner Alamo Corporation

Lease Name Conner Well No. 1

Office Address Box 985, Liberal, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed December 3, 1957 19

Application for plugging filed December 3, 1957 19

Application for plugging approved December 3, 1957 (By phone) 19

Plugging commenced December 4, 1957 19

Plugging completed December 4, 1957 19

Reason for abandonment of well or producing formation No commercial beds encountered

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation None Depth to top Bottom Total Depth of Well 5950 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	1565	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole was filled with heavy mud to 550 feet. A cement plug was set at 550 feet with 25 sacks of cement. Hole was filled with heavy mud to 30 feet. Wooden plug was placed at 30 feet with Rotary Kelly. 5 Sacks of hulls were dumped on plug and pipe was filled with 20 sacks of cement to base of seller.

DEC 7 1957
12-7-1957
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor: Midwestern Drillers

Address: Liberal, Kansas

STATE OF Kansas, COUNTY OF Seward, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Lloyd Henderson

(Address)

SUBSCRIBED AND SWORN to before me this 6 day of December, 1957

My commission expires March 30, 1961 Mary Lane Notary Public.

PLUGGING
FILE SEC 29 T33 R294
BOOK PAGE 67 LINE 25