

STATE OF KANSAS
STATE CORPORATION COMMISSION
Finney State Office Building
30 South Market, Rm 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-119-10126-00-00
API NUMBER 1511910126

LEASE NAME BEHNKE

WELL NUMBER B1-30

4570 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 30 TWP. 33S RGE 29 (E) or ()

COUNTY MEADE

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS 701 S TAYLOR, STE 400 AMARILLO, TX 79101

PHONE # (806) 457-4600 OPERATORS LICENSE NO. 4549

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed 9-23-1957

Plugging Commenced 12-18-2002

Plugging Completed 12-24-2002

The plugging proposal was approved on 12-12-2002 (date)

by RICHARD LACEY (KCC District Agent's Name).

Is AC0-1 filed? YES If not, is well log attached?

Producing Formation MORROW Depth to Top 5727 Bottom 5806 T.D. 6020

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
MORROW	GAS	5727	5806	8-5/8	1645	0
				5-1/2	6000	0

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. SET CIBP AT 5670. DUMP 2 SXS CMT ON CIBP. PERF 5-1/2 CSG AT 1000 WITH 4 SPF. PUMP 340 SXS CMT AT 400 PSI. CIRCULATE CMT TO SURFACE. CUT OFF AND CAP CSG 4 BELOW GL. KCC REP. S. ELBERG.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor ALLIED CEMENTING License No.

Address PO BOX 31 RUSSELL, KS 67665 PHONE: (785) 483-2627

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF TEXAS COUNTY OF POTTER, ss.

CRAIG R. WALTERS, P.E., DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Craig R. Walters
CRAIG R. WALTERS, P.E., DIV. PROD. ENGINEER

(Address) 701 S. TAYLOR, STE 400 AMARILLO, TX 79101

SUBSCRIBED AND SWORN TO before me this 10 day of January, 20 03



(Signature) Lori Pearson
Notary Public

My Commission Expires: 2/26/05

OR