

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 Finney State Office Building  
 130 South Market, Rm 2078  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-129-215240000

LEASE NAME BENNETT "B"

WELL NUMBER 7

660 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 36 TWP. 34 RGE 42 ( E ) or ( W )

COUNTY MORTON

Date Well Completed 8-12-97

Plugging Commenced 8-12-97

Plugging Completed 8-13-97

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # ( 316 ) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-12-97 (date)

by STEVE MIDDLETON (KCC District Agent's Name)

Is ACO-1 filed? YES If not, is well log attached? \_\_\_\_\_

Producing Formation NONE Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 5300

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	1454	NONE

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set. TIH W/4 1/2" DP TO 2800' & SET 100 SKS 60/40 POZMLX, 6%GEL @ 2800', TOH TO 1480' & SET 50 SKS, TOH TO 400' & SET 40 SKS, TOH TO 40' & SET 10 SKS FROM 40' TO 0'. SET 10 SKS IN MH & 15 SKS IN RH. CUT OFF 8 5/8" CSG 3' BELOW GI AND CAP, PERMANENTLY INSCRIBE WELL NAME, NUMBER AND DATE PLUGGED ON CAP. KCC REP: STEVE MIDDLETON.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor CHEYENNE DRILLING License No. 5382

Address P.O. BOX 916, GARDEN CITY, KANSAS 67846 PHONE: (405) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.

L. MARC HARVEY, DRILLING TECHNICAL ASSISTANT (Employee of Operator) or (Operator) of above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) L. Marc Harvey

L. MARC HARVEY, DRILLING TECHNICAL ASSISTANT

(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

STATE CORPORATION COMMISSION  
 RECEIVED  
 SUBSCRIBED AND SWORN TO before me this 9th day of October, 1997  
10-14-1997  
OCT 14 1997

Freda L. Hinz  
 Notary Public

My Commission Expires:  
 CONSERVATION DIVISION  
 Wichita, Kansas

