

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER NA  
LEASE NAME BENNETT  
WELL NUMBER 01  
SPOT LOCATION C SW NW  
SEC. 36 TWP. 34 SRGE 42 ~~XX~~ or (W)  
COUNTY Morton  
Date Well Completed 3/20/57  
Plugging Commenced 1/6/85  
Plugging Completed 1/12/85

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Anadarko Production Company  
ADDRESS P. O. Box 351, Liberal, Kansas 67901

PHONE # (316) 624-6253 OPERATORS LICENSE NO. 5469

Character of Well SWD  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing formation NA Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 5055'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Lansing	Saltwater	3708'	3796'	8-5/8"	1848'	-0-
				4-1/2"	4693'	2416'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.  
Spotted down 2-3/8" tbg 25 sx cement and 1/2 sx hulls from 3790' to 3500', cut off 4-1/2" csg, spotted 45 sx cement from 2400' to 2250', 40 sx cement from 1550' to 1425', 30 sx from 600' to 500', 10 sx from 40' to 3'. Cut off and capped well.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargents Casing Pulling Service License No. 6547  
Address 620 S. Lincoln, Liberal, Kansas 67901

STATE OF KANSAS COUNTY OF SEWARD, ss.

Paul Campbell (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Paul Campbell  
Paul Campbell, Division Operations Manager  
(Address) P. O. Box 351, Liberal, KS 67901

BEVERLY J. WILLIAMS  
Seward County, Kansas  
My Appt. Exp. 11/21/86

My Commission expires: November 21, 1986

Subscribed and sworn to before me this 5th day of Feb, 1985  
Beverly J. Williams  
Notary Public  
STATE CORPORATION COMMISSION  
2-7-1985  
FEB 07 1985

Form CP-4  
Revised 06-83



DRILLER'S LOG

WELL NAME: Bennett #01 WELL LOCATION: 3330 ft. North of South Line  
and 660 ft East of West Line, C SW NW, Sec. 36, Twp. 34, Rge 42,  
Morton COUNTY, Kansas ELEVATION: 3501.28' G.L.

COMPANY: Panhandle Eastern Pipe Line Company, Box #979, Liberal, Kansas

CONTRACTOR: Nye & Snell Drilling Company, 208 Patterson Building, Denver, Colorado.

DRILLING COMMENCED: March 1, 1957

PRODUCTION INFORMATION:

DRILLING COMPLETED: March 21, 1957

WELL COMPLETED: April 8, 1957

WELL CONNECTED: Temporarily abandoned

SOURCE OF DATA: Drillers Report

ROTARY LOG

Description of Formation	Top	Bottom	FORMATIONS	Tops
Sand	0	94	Lower Council Grove	2560
Sand shale & red bed	94	555	Wabaunsee	2767
Red bed & shale	555	868	Topeka	2996
Shale & lime	868	1200	Lansing	3481
Lime shale & sand	1200	1491	Cherokee	4212
(Set 8-5/8" surface casing @ 1484' with 850 sacks common cement)			Atoka	4405
Shale	1491	1518	Morrow	4505
Shale red bed & lime	1518	2098	Upper Morrow SS	4566 & 4583
Shale & lime	2098	5055 TD	Morrow "G" SS	4914 & 4932
(Set 4 1/2" production casing @ 4693' with 225 sacks pozzix cement)			Morrow "Keyes" SS	4988 & 5015
			Mississippian	5021

PERFORATIONS

4578 to 4580 and squeezed  
4568 to 4573  
4292 to 4301

WELL TREATMENT RECORD

Acidized with 500 gallons 15% acid 4/6/57  
Acidized with 500 gallons 15% acid 4/7/57

RECEIVED  
STATE CORPORATION COMMISSION

OCT 19 1957

CONSERVATION DIVISION  
Wichita, Kansas