

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 11-23-56

LEASE NAME TALOGA MORROW "G"

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 501

660 Ft. from S Section Line

1980 Ft. from E Section Line

LEASE OPERATOR Anadarko Petroleum Corporation

SEC. 35 TWP. 34S RGE. 42 ~~W~~ or (W)

ADDRESS P.O. Box 351, Liberal, Kansas 67905-0351

COUNTY Morton

PHONE# (316) 624-6253 OPERATORS LICENSE NO. 4549

Date Well Completed 11-23-56

Character of Well Oil

Plugging Commenced 9-24-91

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 9-26-91

The plugging proposal was approved on 9-23-91 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation Morrow "G" Depth to Top 4553 Bottom 4565 T.D. 4660

Show depth and thickness of all water, oil and gas formations.

RECEIVED
KANSAS CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS

CASING RECORD

OCT 23 1991

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	1505	0
				5 1/2"	4616	2200

CONSERVATION DIVISION
WICHITA, KS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. TIH w/1 1/4" tbg to 4500'. Ld hole w/9 ppg drlg mud. Pmp 1 sx hulls & 25 sxs cmt from 4500'-4300'. TOH w/100 jts 1 1/4" tbg. TOH w/remaining 1 1/4" tbg, shot 5 1/2" csg off @ 2200'. Pmpd 30 sxs cmt from 2200'-2100'. pmpd 40 sxs cmt from 1540'-1440', pmpd 30 sxs cmt from 650'-550', pmpd 10 sxs cmt from 40'-0'. Rec 70 jts of 5 1/2" csg. Cut off & capped 8 5/8" csg 3' below ground level.

(If additional description is necessary, use BACK of this form.) (over)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address 620 S. Lincoln, Liberal, Kansas 67901

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kansas COUNTY OF Seward, ss.

Beverly J. Williams, Engineering Technician (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Beverly J. Williams

(Address) P.O. Box 351, Liberal, KS 67905-0351

SUBSCRIBED AND SWORN TO before me this 21st day of October, 19 91

Cheryl Steers
Notary Public

My Commission Expires: _____

