

15-129-10571-0001

STATE OF KANSAS
STATE CORPORATION COMMISSION
Finney State Office Building
130 South Market, Rm 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

KANSAS RECEIVED
TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days
11-14-97 11:58

API NUMBER NA (SPUD 12/10/55)
LEASE NAME WATSON
WELL NUMBER 1-35
1320 Ft. from S Section Line
3960 Ft. from E Section Line
SEC. 33 TWP. 34S RGE 42 (E) or (W)

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION
ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351
PHONE # (316) 624-6253 OPERATORS LICENSE NO. 4549

COUNTY MORTON
Date Well Completed 1956
Plugging Commenced 10/20/97
Plugging Completed 10/23/97

Character of Well GAS - IWS
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 09/26/97 (date)
by MR. STEVE DURRANT (KCC District Agent's Name)

Is AC0-1 filed? YES If not, is well log attached? _____

Producing Formation GREENWOOD Depth to Top 2882' Bottom 2992' T.D. 4680'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
GREENWOOD	GAS	2882'	2992'	8-5/8"	1506'	4'
				5-1/2"	4680'	2184'

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set. MIRU POLE & PMP TRUCK. DIG CELLAR & PIT. MIXED 3 SXS HULLS & 25 SXS CMT TO PLG PERES FROM 2882-2682'. PLG WENT OUT BTM. RU JACKS. MIXED 3 SXS HULLS & 25 SXS CMT. FOLLOWED PLG W/WIRELINE TO 2575'. DID NOT LOAD HOLE BEHIND PLG. TAG PLG @ 2575. LD HOLE W/MUD. SHOT 5-1/2" OFF @ 2184'. MIXED 35 SXS CMT. CMT PLG FROM 2180-2080. PULLED TO 1540' & MIXED 50 SXS CMT. PLG FROM 1540-1320. PULL TO 690'. MIXED 50 SXS CMT. PLG FROM 690-590. PULLED 68 JTS 5-1/2". LD HOLE W/MUD TO 40'. MIX 10 SXS CMT. PLG 40-4'. CUT OFF & CAP 8-5/8" 4' BELOW GL. RDMO POLE & PMP TRUCK. INSCRIBE CAP. RESTORE LOCATION. KCC REP STEVE DURRANT NOTIFIED 10-20-97.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT & HORTON PLUGGING, INC. License No. 31151

Address RT. 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE: (405) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.

JOHN A. BROMAN, DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John A. Broman
JOHN A. BROMAN, DIVISION PRODUCTION ENGINEER

(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 13th day of November, 1997

Surety Chislers
Notary Public

My Commission Expires: 11/14/98