

15-129-10570-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
209 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 5-6-57

LEASE NAME TALOGA MORROW "G"

WELL NUMBER 603

1980 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 35 TWP. 34S RGE. 42 REXOR(W)

COUNTY Morton

Date Well Completed 5-6-57

Plugging Commenced 10-3-91

Plugging Completed 10-4-91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P.O. Box 351, Liberal, Kansas 67905-0351

PHONE# (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-2-91 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Morrow "G" Depth to Top 4516 Bottom 4526 T.D. 4630

Show depth and thickness of all water, oil and gas formations.

RECEIVED
KANSAS CORPORATION COMMISS

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	1500	0
				5 1/2"	4627	2425

OCT 23 1991

CONSERVATION DIVISION
WICHITA, KS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
TOH w/1 1/4" tbg to 4500'. Ld hole w/ 9 ppg drlg mud. Pmp 1 sx hulls & 25 sxs cmt from 4500'-4300'
TOH w/1 1/4" tbg. Shot off 5 1/2" csg @ 2425'. Pmpd 30 sxs cmt from 2400'-2300', pmpd 40 sxs
cmt from 1540'-1440. Pmpd 30 sxs cmt from 650'-550', pmpd 10 sxs cmt from 40'-0'. Rec 77 its of
5 1/2" csg. Cut off & capped 8 5/8" csg 3' below ground level. KCC Rep - Glenn Barlow. Restore
(If additional description is necessary, use BACK of this form.) Location.

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address 620 S. Lincoln, Liberal, Kansas 67901

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kansas COUNTY OF Seward, ss.

Beverly J. Williams, Engineering Technician (Employee of Operator) or (Operator) or above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Beverly J. Williams
Beverly J. Williams, Eng. Tech.
(Address) P.O. Box 351, Liberal, KS 67905-0351

SUBSCRIBED AND SWORN TO before me this 21st day of October, 1991

Cheryl Steers
Notary Public

My Commission Expires:

