

15-129-10550-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 12-5-58

LEASE NAME Taloga Morrow "G"

WELL NUMBER 304

4620 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 35 TWP. 34S RGE. 42 ~~XX~~or(W)

COUNTY Morton

Date Well Completed 12-5-58

Plugging Commenced 9-5-91

Plugging Completed 9-7-91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P. O. Box 351, Liberal, Kansas 67905-0351

PHONE# (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-4-91 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Morrow "G" Depth to Top 4529 Bottom 4556 T.D. 4625

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORD **RECEIVED** CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	<u>10-16-1991</u>					
	<u>OCT 16 1991</u>			<u>8 5/8</u>	<u>1433</u>	<u>0</u>
				<u>5 1/2</u>	<u>4624</u>	<u>2410</u>

Describe in detail the material which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set TIH W/1-1/4" tbg to 2100'. TIH w/1-1/4" tbg to 4500'. Ld hole w/9 ppg DM, pmpd 2 sxs hulls + 25 sxs cmt from 4500'-4300'. TOH W/1-1/4" tbg, shot 5-1/2 csg off @ 2410' (freepoint). Pmpd 30 sxs cmt from 2400'-2300'. pmpd 40 sxs cmt from 1470'-1370', pmpd 30 sxs cmt from 650'-550'. pmpd 10 sxs cmt from 40'-3'. Rec 66 jts 5-1/2" csg. Cut off & capped 8-5/8" csg 3' below GL. (over)
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address 620 S. Lincoln, Liberal, Kansas 67901

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kansas COUNTY OF Seward, ss.

Beverly J. Williams, Engineering Technician (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Beverly J. Williams

Beverly J. Williams, Eng. Tech.

(Address) P.O. Box 351, Liberal, KS 67905-0351

SUBSCRIBED AND SWORN TO before me this 14th day of October, 19 91

Cheryl Steers
Notary Public

My Commission Expires: 6-93



