

15-129-10479-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 11-7-58

LEASE NAME TALOGA MORROW "G"

WELL NUMBER 403

3300 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 35 TWP. 34S RGE. 42 ~~XX~~or(W)

COUNTY Morton

Date Well Completed 11-7-58

Plugging Commenced 9-20-91

Plugging Completed 9-23-91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P.O. Box 351, Liberal, Kansas 67905-0351

PHONE#(316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-19-91 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation Morrow "G" Depth to Top 4561 Bottom 4563 T.D. 5054

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled Out |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8" | 1451 | 0 |
| | | | | 4 1/2" | 4621 | 2024 |
| | | | | | | |

RECEIVED

STATE CORPORATION COMMISSION

OCT 23 1991

CONSERVATION DIVISION
WICHITA, KS

Describe in detail the manner in which the well was plugged, indicating where the plugs were placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set TIH w/1 1/4" tbg to 4500'. Ld hole w/9 ppg drlg mud. Pmp 1 sx hulls & 20 sxs cmt from 4500'-4300'. TOH w/1 1/4" tbg, shot 4 1/2" csg off @ 2024'. Pmpd 30 sxs cmt from 2000'-1900', pmpd 40 sxs cmt from 1500'-1400', pmpd 30 sxs cmt from 650'-550', pmpd 10 sxs cmt from 40'-0'. Rec 63 jts of 4 1/2" csg. Cut off & capped 8 5/8" csg 3' below ground level. KCC Rep - Glenn Barlow. Restore location.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address 620 S. Lincoln, Liberal, Kansas 67901

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kansas COUNTY OF Seward, ss.

Beverly J. Williams, Engineering Technician (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct; so help me God.

(Signature) Beverly J. Williams
Beverly J. Williams, Eng. Tech.
(Address) P.O. Box 351, Liberal, KS 67905-0351

SUBSCRIBED AND SWORN TO before me this 21st day of October, 19 91

My Commission Expires: _____
Cheryl Steers
Notary Public

