

15-129-10549-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 11-19-58

LEASE NAME Taloga Morrow "G"

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 303

3300 Ft. from S Section Line

3300 Ft. from E Section Line

LEASE OPERATOR Anadarko Petroleum Corporation

SEC. 35 TWP. 34S RGE. 42 KRX or (W)

ADDRESS P. O. Box 351, Liberal, Kansas 67905-0351

COUNTY Morton

PHONE# (316) 624-6253 OPERATORS LICENSE NO. 4549

Date Well Completed 11-19-58

Character of Well Oil

Plugging Commenced 9-11-91

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 9-16-91

The plugging proposal was approved on 9-10-91 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Morrow "G" Depth to Top 4504 Bottom 4548 T.D. 4673

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	From	To	Size	Put in	Pulled out
KANSAS CORPORATION COMMISSION OCT 16 1991			8 5/8	1425	853
			5 1/2	4630	2220

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the methods or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. TIH w/1-1/4" tbg to 450'. Ld hole w/9 ppg DM, pmpd 1 sx hull & 25 sxs cmt from 4500'-4300'. TOH w/1-1/4" tbg to 300'. TOH w/1-1/4" tbg, shot 5-1/2" csg off @ 2220' (freepoint). Pmpd 30 sxs cmt from 2200'-2100'. pmpd 40 sxs cmt from 1470'-1370'. rec 72 jts 5-1/2" csg. Shot off 8-5/8" csg @ 853' (freepoint). Rec 26 jts 8-5/8" csg. TIH w/1-1/4" tbg to 450'. Pmpd 45 sxs cmt from  
(If additional description is necessary, use BACK of this form.) (over)

Name of Plugging Contractor Sargents Casing Pulling Service License No. 6547

Address 620 S. Lincoln, Liberal, Kansas 67901

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kansas COUNTY OF Seward, ss.

Beverly J. Williams, Engineering Technician (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Beverly J. Williams  
Beverly J. Williams, Eng. Tech.

(Address) P.O. Box 351, Liberal, KS 67905-0351

SUBSCRIBED AND SWORN TO before me this 14th day of October, 19 91

Cheryl Steers  
Notary Public

My Commission Expires:



450'-400' inside 13-5/8" csg. TOH w/tbg to 30', pmpd 20 sxs cmt from 30'-3'. TOH w/1-1/4" tbg. Cut off and capped 13-5/8" csg 3' below GL. KCC Rep - Glenn Barlow.