


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Morton County, Sec. 35 Twp. 34S Rge. (E) 42 (W)

Location as "NE/CNW/SW" or footage from lines G SW NE
Lease Owner Anadarko Production Company
Lease Name Hall Well No. 01
Office Address Box 351 Liberal, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 4-8 19 58
Application for plugging filed 1-12 19 66
Application for plugging approved 1-14 19 66
Plugging commenced 2-12 19 66
Plugging completed 2-12 19 66
Reason for abandonment of well or producing formation Non economical



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 10-31 19 63
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ed Eves
Producing formation Morrow "G" Sand Depth to top 4636 Bottom 4667 Total Depth of Well 4720 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Morrow "G" Sand	Oil	4636'	4667'	8-5/8"	1408'	
				5-1/2"	4703'	3230'
				2-3/8"	4651'	4651'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mixed 20 sxs cement & pumped plug to 4160' with heavy mud.
Shot off 5-1/2" casing at 3230'. Pulled casing to 700'.
Spotted 35 sxs cement from 700' - 600' thru 5-1/2" casing.
Finished pulling casing. Filled hole with mud to 45'.
Spotted 15 sxs cement from 45' to surface.
Complete @ 5:00 p.m. 2/12/66.

RECEIVED
STATE CORPORATION COMMISSION
MAR 3 1966
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sargent's Casing Pulling Service
Address 1546 Clay Courts Liberal, Kansas

STATE OF Kansas, COUNTY OF Seward, ss.
V. K. Downey (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) V. K. Downey

(Address) _____

SUBSCRIBED AND SWORN TO before me this 28th day of February, 1966

My commission expires My Commission Expires Sept. 29, 1968

Donald L. Vanjiman
Notary Public.

15-129-10477-0000

DRILLER'S LOG

WELL NAME: Hall #01; COMPANY OPERATING: Anadarko Production Company
 ADDRESS of COMPANY: Box 351 Liberal, Kansas

WELL LOCATION: C 1/2 SW 1/2 NE 1/2,
3300 ft. North of South line,
3300 ft. East of West line; Sec. 35, Twp. 34S, Rge. 42W, Morton County, Kansas

DRILLING STARTED 2-28, 1958; DRILLING COMPLETED 3-20, 1958
 WELL COMPLETED 4-8, 1958; WELL CONNECTED _____, 19____

ELEVATION: 3505 ft. Ground Level; CHARACTER OF WELL (Oil, Gas, or Dry Hole) Oil

OIL OR GAS SANDS OR ZONES - PERFORATIONS - ACIDIZING AND FRACTURING INFORMATION					
Name	From	To	No. of Shots	Gallons Used	Kind Used
Morrow G Sand	4636	4667	4		

CASING RECORD

Size	Amount Set	Sacks of Cement	Amount Pulled
8-5/8"	1408'	800	0
5-1/2"	4703'	200	0

FORMATION RECORD

Formation	Top	Bottom	Formation	Top	Bottom
Wabaunsee	2705	2907			
Topeka	2907	3162			
Greenwood Lansing	3162	3346			
Lansing	3346				
Cherokee	4001				
Morrow Shale	4222	4709			
Morrow G Sand	4281	4303			
Morrow G Sand	4636	4667			
Morrow Keyes Sand	4678	4707			
Mississippian	4709				

STATE OF KANSAS
 CONSERVATION DIVISION
 MAR 3 1958
 Liberal, Kansas

RESULTS of INITIAL PRODUCTION TEST: Waiting on State Test
 This is a copy of the original Driller's Log filed April 8, 1958.