

15-129-10478-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

CORRECTED COPY

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Morton County, Sec. 35 Twp. 34 Rge. 42 (E) (W)

Location as "NE/CNW'SW" or footage from lines C NW NE

Lease Owner Anadarko Production Company

Lease Name Hall Well No. 02

Office Address P. O. Box 351, Liberal, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed December 15 1962

Application for plugging filed October 27 1962

Application for plugging approved October 29 1962

Plugging commenced October 29 1962

Plugging completed October 30 1962

Reason for abandonment of well or producing formation Non-commercial

If a producing well is abandoned, date of last production October 22 19 62

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh E. Scott

Producing formation Morrow "G" Depth to top 4724 Bottom 4798 Total Depth of Well 4819 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Morrow "G"	Oil	4726	4756	8 5/8"	1405	None
				4 1/2	4818	2847

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged bottom with 3 yards gravel + 5 sacks cement, top of cement at 4650'. Filled hole with mud, spotted 35 sacks from 824' to 700', spotted 15 sacks from 54' to 5'.

RECEIVED
STATE CORPORATION COMMISSION
11-6-1962
NOV 6 1962

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sargent's Casing Pulling Service

Address 121 West Ninth Street, Liberal, Kansas

STATE OF KANSAS, COUNTY OF SEWARD, ss.
S. H. Neithercoat (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) S. H. Neithercoat
S. H. Neithercoat, Superintendent
P. O. Box 351, Liberal, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 2nd day of November, 19 62

My commission expires

Notary Public.

MY COMMISSION EXPIRES SEPT. 29, 1964


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. PANHANDLE EASTERN PIPE LINE CO.
Farm. Hall No. 02

SEC. 35 T. 34 R. 42W
C NW NE
4620' N of SL, 3300' E of WL

Total Depth. 4819'
Comm. 11-15-58 Comp. 12-3-58
Shot or Treated.
Contractor. Holm Drig. Co.
Issued. 3-21-59

County Morton
KANSAS



Elevation. 3498' GL

Production. 10 BOPD

CASING:

8 5/8" 1405' cem w/800 sx.
4 1/2" 4818' cem w/85 sx.

Figures Indicate Bottom of Formations.

surface clays 500
red bed 810
red bed, sand & shells 1350
shale & shells 2790
shale & lime 4815
lime 4819
Total Depth

TOPS:

Base Cimarron Anhydrite 1399 (scout)
Wabaunsee (scout) 2714
Topeka 2918
Lansing 3387
Cherokee 4066
Morrow Shale 4325
Morrow F. Sand 4618-4625
Morrow G Sand 4724-4762
Morrow G Sand 4774-4798
Keyes 4807

OIL OR GAS SAND OR ZONES - PERFORATIONS - ACIDIZING AND FRACTURING INFORMATION

Name	From	To	No. of Shots	Gallons Used	Kind Used
Morrow G Sand	4777	4782	20	300	15%
Morrow G Sand	4726	4756	120	1000	15%

F/2 000 gelled lease crude
F/10 000 gelled lease crude