

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Morton SEC. 35 TWP. 34S RGE. 42 E/W
Location as in quarters or footage from lines:
C NE SE

Lease Owner Anadarko Production Company
Lease Name WESTERFIELD Well No. 04
Office Address P. O. Box 351, Liberal, Kansas 67901
Character of Well (Completed as Oil, Gas or Dry Hole): Oil
Date Well Completed November 29, 1956
Application for plugging filed October 28, 1981
Plugging commenced May 13, 1982
Plugging completed May 17, 1982
Reason for abandonment of well or producing formation Depleted

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Paul Luthi
Producing formation Morrow "C" Depth to top 4576 bottom 4592 T.D. 5023
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Morrow "C"	Oil	4576	4592	8-5/8"	1472'	-0-
				5-1/2"	5020	40'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Spot 60 sxs cmt 4592. to 4000, pulled 1 it 5-1/2" casing, shot hole in 5-1/2" casing @
2500, spot 35 sxs cmt 2500 to 2300, 40 sxs cmt 1600 to 1300, 25 sxs cmt 600 to 400,
spot 10 sxs cmt 40-3, cut off & cap well.

RECEIVED
STATE CORPORATION COMMISSION
6-11-1982
IN 11 1502

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Sargents Casing Pullers

STATE OF KANSAS COUNTY OF SEWARD, ss.
L. E. Townley (employee of owner) or ~~(owner)~~ of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) L. E. Townley
P. O. Box 351, Liberal, Kansas 67901
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of June, 19 82

BEVERLY J. WILLIAMS
Seward County, Kansas
My Commission expires: March 21, 1982

Beverly J. Williams
Notary Public.

My Commission expires:

DRILLER'S LOG

15-129710575-0000

Well Name Westerfield #01

Company Panhandle Eastern Pipe Line Co.

Well Location Center NE SE of

Contractor Nye & Snell Drlg Co.

Section 35-34S-12W

Elevation 3515.07

County Morton State Kansas

Drilling Commenced November 10, 1956

Swab Test Swbd 100 BO in 1 1/2 hrs from lower perf & 18 BOPH from top perfs.

Drilling Completed December 2, 1956

Method of Production Swabbing

Well Completed December 29, 1956

Source of Data Driller's Report

Well Connected

ROTARY LOG

Description of Formation

Top

Bottom

Sand and shale	0	203
Red bed & shale	203	600
Red bed & lime	600	935
Red bed, lime & shale	935	1248
Shale & lime	1248	1420
Lime shale & gyp	1420	1481
Shale & red bed	1481	2015
Lime & shale	2015	4240
Coring	4240	4286
Lime & shale	4286	4533
Coring	4533	4580
Lime & shale	4580	4593
Coring	4593	4653
Lime & shale	4653	5023

FORMATION TOPS

Wabaunsee	2791
Topeka	3002
Eansing	3264
Cherokee	4204
Morrow Sh	4499
Morrow S.S.	4512-22
" "	4573-96
" "	4910-33
" "	4954-4973
" "	4994-5028

PERFORATIONS

4576-92
4514-22

WELL TREATMENT RECORD

Frac 5000 gals lease oil
w/2500# sand

CASING RECORD: Set 1472' of 8 5/8" csg w/850 sx common cmt
Set 5020' of 5 1/2" used csg

RECEIVED
STATE CORPORATION COMMISSION

NOV 12 1956

CONSERVATION DIVISION
Wichita Kansas