

15-129-10574-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Morton SEC. 35 TWP. 34S RGE. 42 E/W
Location as in quarters or footage from lines:

C SE SE

		35	

Lease Owner Anadarko Production Company
Lease Name WESTERFIELD Well No. 03
Office Address P. O. Box 351, Liberal, Kansas 67901
Character of Well (Completed as Oil, Gas or Dry Hole): oil
Date Well Completed December 19, 1956
Application for plugging filed October 28, 1981
Plugging commenced May 15, 1982
Plugging completed May 20, 1982
Reason for abandonment of well or producing formation

Locate Well
correctly on above
Section Platt.

Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Paul Luthi
Producing formation Morrow "C" Depth to top 4520 bottom 4537 T.D. 5080

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
<u>Morrow "C"</u>	<u>Oil</u>	<u>4520</u>	<u>4537</u>	<u>8-5/8"</u>	<u>1473'</u>	<u>-0-</u>
				<u>5-1/2"</u>	<u>4599'</u>	<u>3021'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Spotted 25 sxs cmt & 2 sxs hulls from 4537 to 4300, shot off 5-1/2" csg @ 3021, pulled
84 jts, spotted 25 sxs cmt 2950-2800, spot 50 sxs cmt 1723-1423, spot 25 sxs cmt 600-
500, spot 10 sxs cmt 40-3, cut off csg & cap well.

RECEIVED

STATE CORPORATION COMMISSION

6-11-1982

JUN 11 1982

CONSERVATION DIVISION

Wichita Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sargents Casing Pullers

STATE OF KANSAS COUNTY OF SEWARD, ss.

L. E. Townley (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.


(Signature)

P. O. Box 351, Liberal, Kansas 67901
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of June, 19 82

Beverly J. Williams
Notary Public.

My Commission Expires November 21, 1982



REFERS TO Drieler's Log

Well Name Westerfield #02 Company Panhandle Eastern
 Well Location Center SE 1/4 Contractor Ray & Sull Delyle
Sec. 35, Twp. 34, Range 42 Elevation 3,520.81
 County Marion State Kansas Drilling Commenced Dec 3-56
Preliminary Test Showed 75 BOPH Drilling Completed Dec 19
 Method of Production Flowed Well Completed Dec 28-56
 Source of Data Drieler's Report Well Connected _____

Rotary Log

Description of Formation	Top	Bottom
Sand shale & red bed	0	375
red bed & shale	375	715
red bed & lime	715	940
Lime & shale	940	1479
red bed & shale	1479	1645
Shale	1645	2310
Lime & shale	2310	4362
Lime & shale	4362	5080 TD

Formation Tops

<u>Wabaussee</u>	<u>2767</u>	<u>Lower Morrow Sd.</u>
<u>Topeka</u>	<u>2975</u>	<u>4902-11</u>
<u>C 50 Lansing</u>	<u>3238</u>	<u>Lower Morrow Sd. 4944-72</u>
<u>Lansing</u>	<u>3450</u>	<u>Keyes 4995-50</u>
<u>Cherokee</u>	<u>4160</u>	<u>Missippian 5051</u>
<u>Morrow</u>	<u>4454</u>	
<u>Upper Morrow Sd.</u>	<u>4511-40</u>	
<u>Upper Morrow Sd.</u>	<u>4781-96</u>	

RECEIVED
STATE CORPORATION COMMISSION
NOV 1956

CALCULATION SHE.

Sheet _____ of _____

Date _____ 19 _____

Made By _____

Checked By _____ Date _____

REFERS TO _____

*Perforations
4527 - 4537*

*Well Treatment Record
Well was not treated*

*Casing Record :
Ran 1473' of 8 7/8" surf. cas w/875
sp. common cement
Ran 4493' of 2-7/8" Tby rods*

RECEIVED
STATE CORPORATION COMMISSION

NOV 12 1931

CONSERVATION DIVISION
Wichita, Kansas