

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 Finney State Office Building
 130 South Market, Rm 2078
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-129-20,765 - 0000

LEASE NAME TALOGA UNIT

WELL NUMBER 503

1320 Ft. from S Section Line

2540 Ft. from E Section Line

SEC. 35 TWP. 34S RGE. 42 (X) or (W)

COUNTY MORTON

Date Well Completed 2/05/86

Plugging Commenced 2/12/96

Plugging Completed 2/14/96

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # (316) 624-6253 OPERATORS LICENS NO. 4549

Character of Well INJECTOR

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1/31/96 (date)

by RICHARD LACEY (KCC District Agent's Name)

Is ACO-1 filed? YES If not, is well log attached? _____

Producing Formation MORROW "G" (INJ. FORM.) Depth to Top 4526' Bottom 4538' T.D. 4700'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
MORROW "G"	OIL	4526'	4538'	8-5/8"	1390'	
				4-1/2"	4695'	2580'

RECEIVED
 KANSAS DRP COMM
 1996 MAR - 7 A.M. 11:49
 03-7-1996

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.
P&A'D AS FOLLOWS: MIRU CSG PULLERS, MIX 2 SXS HULLS AND 20 SXS CMT. SPOT PLUG FROM 4526'-4326'. SHOT OFF 4-1/2" CSG @ 2580'. PULL CSG TO 1420'. CIRC HOLE W/9PPG MUD. PMP 50 SXS CMT FROM 1420'-1270'. PMP 40 SXS CMT FROM 650'-550'. PMP 10 SXS CMT FROM 40'-3'. CUT OFF & CAP 8-5/8" CSG 3' BELOW GROUND LEVEL.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT & HORTON PLUGGING, INC. License No. 31151

Address RT. 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE: (405) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.

John M. Dolan, Sr. Technical Assistant (Employee of Operator) or (Operator) of above-described well,
 being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John M. Dolan
 (Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 6th day of March, 1996

Freda L. Hinz
 Notary Public

My Commission Expires:

