

19028

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202RECEIVED
STATE CORPORATION COMMISSION
NOV 25 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Cleary Petroleum Corporation

Complete Address: 310 Kermac Bldg., Oklahoma City, Oklahoma

Lease Name Classen Well No. 1

Location C SE Sec. 36 Twp. 33 Rge. 27 (E) (W)

County Meade Total Depth 6015'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A X

Other well as hereafter indicated: None

Plugging Contractor: Lillard Pipe Pullers

Address: Box 962, Woodward, Oklahoma License No. 618

Operation Completed: Hour 5:00PM Day 21 Month 11 Year 1968

The Above well was plugged as follows:

8 5/8" to 1623' circulated w/ cement. 4 1/2" to 5959' cemented.

Top perforations 5932' Plug bottom w/ 15 sacks cement

Top of cement 5600' Mud 5600' to 700'

Spotted 35 sacks cement 700' to 600' Mud 600' to 40'

Plug, Halls & 10 sacks cement 40' to 0'. Halliburton Pump Truck,

Pulled 5426' of 4 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edgar A. Evers
Well Plugging SupervisorDATE 11/26/68
INV. NO. 8891-11