

P

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -175 - 20,299 (of this well)

Operator's Full Name Yucca Petroleum Co.

Complete Address P.O. Box 2585, Amarillo, Texas 79105

Lease Name Hattie Jones Well No. 2-15

Location C SW SW Sec. 15 Twp. 32 Rge. (E) 33 (W)

County Seward Total Depth 6000

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Midwest Casing Pulling

Address Box F, Sublette, KS 67877 License No. 766

Operation Completed: Hour _____ Day 18 Month 3 Year 78

The above well was plugged as follows:

Cast iron bridge plug set@ 4215' w/ 10' of cement on top

Mud 4215' to 1500', spotted 35 sxs cement 1500' to 1400'

Mud 1400' to 45', put bridge & 15 sxs. cement 45' to 0'

Cut off 85/8" 42" below ground level.

Recovered 1640' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed *Frank Brundage*
Well Plugging Supervisor

DATE 11-4-78

INV. NO. 7048-W