

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM  
(File One Copy)

API NUMBER 15-175-20457-0000 (of this well) 6/86  
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Amoco Production Company OPERATORS LICENSE NO. 5952

ADDRESS P. O. Box 432, Liberal, Kansas 67901 PHONE # (316) 624-6241

LEASE (FARM) Edna Scott WELL NO. 3 WELL LOCATION C. NE. SE COUNTY Seward

SEC. 15 TWP. 32 RGE. 33 (E) of (W) TOTAL DEPTH 6000 PLUG BACK TD 5948

Check One:

OIL WELL  GAS WELL  D & A  SWD or INJ WELL  DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 8 5/8 SET AT 1616 CEMENTED WITH 700 SACKS

CASING SIZE 5 1/2 SET AT 6000 CEMENTED WITH 650 SACKS

PERFORATED AT 5780 to 5792

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL \_\_\_\_\_

See procedure on back side.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes  
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 9/30/85

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Barry Baggett

PHONE # (316) 624-6241

ADDRESS P. O. Box 432, Liberal, Kansas 67901

PLUGGING CONTRACTOR To be bid. LICENSE NO. \_\_\_\_\_

ADDRESS \_\_\_\_\_ PHONE # ( ) \_\_\_\_\_

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Paul Johnson  
(Operator or Agent)

SEP 25 1985

DATE: 9/23/85

CONSERVATION DIVISION  
Wichita, Kansas

(1)



JOHN CARLIN  
MICHAEL LENNEN  
ANGALEE WRIGHT  
KEITH R. HENLEY  
JUDITH A. McCONNELL  
IRIAN J. MOLINE

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary  
General Counsel

## State Corporation Commission

### CONSERVATION DIVISION

(Oil, Gas and Water)  
200 Colorado Derby Building  
202 West 1st Street  
WICHITA, KANSAS 67202-1286

THIS NOTICE

DECEMBER 6 1985

September 26, 1985

EXPIRES

WELL PLUGGING NOTICE

Edna Scott #3  
C NE SE  
Sec. 15-32S-33W  
Seward County

Amoco Production Company  
P. O. Box 432  
Liberal, KS 67901

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in cursive script that reads "William R. Bryson".

William R. Bryson, Director

Please submit your proposal for plugging the above captioned well to  
DIST. #1 302 West McArtor Dodge City, KS 67801 316-225-6760  
five days prior to plugging the well (KAR-82-3-113).



Amoco Production Company

August 27, 1985

File: RAR-736-400.1

Recommended Plugging Procedure

Edna Scott No. 3

Section 15-T32S-R33W

Seward County, Kansas

1. Pull the tubing, sucker rods, and pump.
2. Set a CIBP at 5700' and cap with 2 sx of cement.
3. Locate the free point of the casing, cut and pull the casing (estimated to be 3100').
4. Load hole from CIBP to 50' below the casing stub with mud.
5. Set a cement plug from 50' below to 50' above the casing stub with mud.
6. Load hole from cement plug to 3000' with mud.
7. Set a cement plug from 3000' to 2500' to isolate the Hugoton and Council Grove.
8. Load hole from plug to 1676' with mud.
9. Set a cement plug from 1676-1556' to isolate the surface casing.
10. Load hole from plug to 40' below ground level with mud.
11. Set a cement plug from 5-40' below ground level.
12. Cut off casing at 5' and weld on a steel cap with proper identification.
13. Backfill hole and restore surface location .

All cement should be Class "H" and the mud should be at least 9 ppg with a viscosity of 36 cp. Attached is a diagram of the wellbore after plugging operations are complete.

*C. H. Kelm*

C. H. Kelm

BKB/bka

RECEIVED  
STATE CORPORATION COMMISSION

Attachment

SEP 25 1985

CONSERVATION DIVISION  
Wichita, Kansas