

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-175-10054-0000 (of this well) 6/88
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Amoco Production Co. OPERATORS LICENSE NO. 5952

ADDRESS P. O. Box 432 PHONE # (316) 624-6241

LEASE (FARM) Kansas University ^{G.U.D.} WELL NO. 2 WELL LOCATION NW/4 COUNTY Seward

SEC. 9 TWP. 32S RGE. 33 (E) or (W) TOTAL DEPTH 2690 PLUG BACK TD 2642

Check One:

OIL WELL _____ GAS WELL X D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8-5/8 SET AT 620 CEMENTED WITH 650 SACKS

CASING SIZE 4.5 SET AT 2689 CEMENTED WITH 1000 SACKS

PERFORATED AT 2582-2634

CONDITION OF WELL: GOOD X POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL See back of form

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Already filed IS ACO-1 FILED? Yes
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN January 26, 1988

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Bob Heath (Amoco Production) PHONE (316) 624-6241

ADDRESS P.O. Box 432 Liberal, KS 67905-0432

PLUGGING CONTRACTOR Midwest Casing LICENSE NO. 6497 6/88

ADDRESS Box F Sublette, KS 67877 PHONE # () _____

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Larry L. Smith
(Operator or Agent)

DATE: 1-15-88

①



Amoco Production Company

January 7, 1988

C. P. Kennedy
Building

File: LRP-2-400.1

Plugging and Abandonment Procedure - Proposed
Kansas University G. U. "D" No. 2
Section 9-32S-33W
Seward County, Kansas

Detailed below is the proposed plugging procedure for the subject well. Depths are relative to the KB elevation (2828') per the Gamma-Contact Caliper Log run by Welex on May 9, 1963. Please note that this procedure is for permitting purposes only.

1. MIRUSU. Pull rods, pump, and tubing.
2. Trip in tubing. Pump a 15 sack cement plug (Class "C" with 2% CaCl_2) from PBDT (2642') to 2480'+/-.
3. Fill hole with 9.0 ppg, 36 qt-sec viscosity mud.
4. Pump a 5 sack cement plug from 40' to 5'. Cut off casing at 5', weld on steel cap with I.D.
5. Restore location.

Note that this well has no salvable casing (due to cement circulation to surface during primary cementing job). A wellbore sketch is attached for your reference. Please contact Brian Powers with questions.

C. H. Kelm

BSP/bka

Attachment

CONSERVATION DIVISION
JAN 19 1988
CONSERVATION DIVISION
Wichita, Kansas

State of Kansas



Kansas Corporation Commission

MIKE HAYDEN
KEITH R. HENLEY
RICH KOWALEWSKI
MARGALEE WRIGHT
JUDITH McCONNELL
FRANK A. CARO, JR.

GOVERNOR
CHAIRMAN
COMMISSIONER
COMMISSIONER
EXECUTIVE DIRECTOR
GENERAL COUNSEL

CONSERVATION DIVISION
SHARI M. FEIST, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

THIS NOTICE

January 20, 1988

KAR 20 '88

WELL PLUGGING NOTICE

EXPIRES

Kansas University G.U.D. #2
NW/4
Sec. 09-32S-33W
Seward County

Amoco Production Company
P. O. Box 432
Liberal, KS 67905


Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

Please contact the district office listed below to review your suggested method of plugging five days prior to plugging the well (KAR-82-3-113).

This notice is void after ninety (90) days from the above date.

Sincerely,



Shari Feist
Director
State Corporation Commission

DISTRICT #1 302 W. McArtor, Dodge City, KS 67801 (316) 225-6760