

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

Rev. 03/92

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 119-20,123-000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date. 8/99

WELL OPERATOR Samedan Oil Corporation KCC LICENSE # 04570
(owner/company name) (operator's)
ADDRESS 9400 N. Broadway, Suite 700 CITY Oklahoma City

STATE Oklahoma ZIP CODE 73114 CONTACT PHONE # (405) 475-2000

LEASE Angell WSW WELL# 1 SEC. 6 T. 33S R. 29 XXXX (West)

SE SW SPOT LOCATION/OOOO COUNTY Meade

677 FEET (in exact footage) FROM S/NX (circle one) LINE OF SECTION (NOT Lease Line)

2176 FEET (in exact footage) FROM S/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL Water Supply Well X
D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 1522' CEMENTED WITH 650 SACKS

PRODUCTION CASING SIZE 5 1/2" SET AT 4057' CEMENTED WITH 398 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 3515' - 3620'

ELEVATION 2707 G.L. T.D. 5900' P.B.T.D. 4016' ANHYDRITE DEPTH 1500'
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Set 25 sxs Class C (60/40/6) cmt plug w/100# cotton seed hulls at 3465'. Displace hole w/9.2 ppg plug mud. Set 50 sxs Class C (60/40/6) cmt plug at 1564'. Set 30 sxs Class C (60/40/6) cmt plug @ 500'. Set 10 sxs Class C (60/40/6) cmt plug from 40'-3'. Cut off surface casing 4' below G.L. Install ID plate (If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Lee Farmer PHONE# (405) 262-7778

ADDRESS Rt. 2, Box 218-B City/State El Reno, OK 73036

PLUGGING CONTRACTOR Sargent's Casing Pulling Service KCC LICENSE # 6547 6/99
(company name) (contractor's)

ADDRESS P. O. Box 506, Liberal, KS 67905 PHONE # (316) 624-7455

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) September 1998

PAYMENT OF THE PLUGGING FEE **RECEIVED** WILL BE GUARANTEED BY OPERATOR OR AGENT
KANSAS CORPORATION COMMISSION

DATE: 8/31/98 AUTHORIZED OPERATOR/AGENT: [Signature]
(signature)

SEP 01 1998

9-1-1998

CONSERVATION DIVISION
WICHITA KS



Kansas Corporation Commission

Bill Graves, Governor John Wine, Chair Susan M. Seltsam, Commissioner Cynthia L. Claus, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

September 1, 1998

Samedan Oil Corporation
9400 N. Broadway, Suite 700
Oklahoma City, Ok. 73114

Angell WSW #1
API 15-11920123
SE SW
Sec. 6-33S-29W
Meade County

Dear Lee Farmer,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in cursive script that reads "David P. Williams".

David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City, KS 67801
(316) 225-8888