

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 03/92

WELL PLUGGING APPLICATION FORM

15-175-10068-0000 (PLEASE TYPE FORM and File ONE Copy)

API # Comp. 10-16-61 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR A. L. Abercrombie, Inc. KCC LICENSE # 5393
(owner/company name) (operator's)

ADDRESS Rt. #1, Box 56 CITY Great Bend

STATE Kansas ZIP CODE 67530 CONTACT PHONE # (316) 793-8186

LEASE Frederick WELL# 5 SEC. 26 T. 33 R. 31 (~~East~~/West)

C - NE - SW - SPOT LOCATION/QQQQ COUNTY Seward County

3310 FEET (in exact footage) FROM S (N) (circle one) LINE OF SECTION (NOT Lease Line)

3200 FEET (in exact footage) FROM (E/W) (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL X GAS WELL D&A SWD/ENHR WELL DOCKET#

CONDUCTOR CASING SIZE SET AT CEMENTED WITH SACKS

SURFACE CASING SIZE 8 5/8 SET AT 1228 CEMENTED WITH 650 SACKS

PRODUCTION CASING SIZE 5 1/2 SET AT 5916 CEMENTED WITH 160 SACKS

DV Tool @ 4460 with 160 sacks
LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: Perf 5848-88 Prod.Pkr. 5830 Perf 4313-18

ELEVATION 2731/2741 T.D. 5920 PSTD 5903 ANHYDRITE DEPTH NA
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD X POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING In compliance with rules and regulations with
State of Kansas.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED?

If not explain why?

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

E. L. Abercrombie PHONE# (316) 316-793-8186

ADDRESS Rt. #1 Box 56 City/State Great Bend, Ks.

PLUGGING CONTRACTOR Kelso Casing Pulling, Inc. KCC LICENSE # 6050
(company name) (contractor's)

ADDRESS Box 347 Chase, Ks. PHONE # () 316-938-2943

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Soon as possible

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 9-16-93 AUTHORIZED OPERATOR/AGENT: E. L. Abercrombie (signature)

RECEIVED
STATE CORPORATION COMMISSION
SEP 21 1993
CONSERVATION DIVISION
Wichita, Kansas

FREDERICK NO. 5
 Panhandle Development Company, Inc.
 Section 26-33s-31w
 Seward County, Kansas

COPY

Casing Record:

Commenced: 9-27-61
 Completed: 10-16-61

8 5/8" O.D. at 1227.73' G.L. with 450
 sacks Pozmix, 2% Gel & 2% C.C. 200 sacks
 common, 2% C.C.
 5 1/2" O.D. at 5916' with 160 sacks Pozmix
 1/2# Flow Seal & 17.7# Salt per sack.

<u>Formation</u>	<u>From</u>	<u>To</u>
Top Soil	0	70
Surface Clay and Sand	70	520
Red Bed and Sand	520	740
Sand and Shale	740	1240
Red Bed and Sand	1240	1485
Red Bed and Anhydrite	1485	1955
Shale and lime	1955	4465
Lime	4465	5442
Lime and Shale	5442	5500
Lime	5500	5920 RTD

State of Kansas)
 County of Seward) SS

I Hereby affirm that the above and foregoing is a true and correct copy of the log of the Frederick No. 5 well, located C-NE-SW of Section 26-33s-31w, Seward County, Kansas.

McCLELLAN DRILLING COMPANY

by [Signature]
 Manager

Subscribed and sworn to before me a notary public this 18th
 day of October, 1961.

[Signature]
 Notary Public - Seward County, Kansas

My Commission expires:
September 26, 1965

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 21 1993
 CONSERVATION DIVISION
 Wichita, Kansas

Joan Finney
Governor

Jim Robinson
Chairman

F. S. Jack Alexander
Commissioner

Rachel C. Lipman
Commissioner

Judith McConnell
Executive Director

Brian Moline
General Counsel



Kansas Corporation Commission

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

September 21, 1993

A L Abercrombie Inc
Rt 1 Box 56
Great Bend KS 67530

Frederick #5
API 15-N/A
3310 FNL 3200 FEL
Sec. 26-33S-31W
Seward County

Dear E. L. Abercrombie,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in cursive script, appearing to read "David P. Williams".

David P. Williams
Production Supervisor

Conservation Division
William R. Bryson
Director
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, Kansas 67202-1286
Telephone (316) 263-3238

District: #1 304 W. McArtor
Dodge City KS 67801
(316) 225-6760